

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

GENERAL CONSTRUCTION SPECIFICATIONS

- 1. PURPOSE AND SCOPE:** The City of Charleston, WV (the City) is soliciting bids for the installation of a new storm sewer system on Chesterfield Ave and Glenridge Road.

The City of Charleston owns and operates a 30-inch storm sewer system that is no longer functioning properly. The system consists of a 30-inch corrugated metal pipe that has deteriorated and a reinforced concrete pipe that was constructed in a manner that causes sediment to accumulate in the system. This project will replace the 30-inch corrugated metal pipe and install a new storm sewer to bypass the reinforced concrete pipe that is not functioning properly. The project also includes, but is not limited to, traffic control, the installation of manholes and inlets.

The work shall consist of the Vendor furnishing all materials, equipment and labor necessary for the satisfactory completion of this project. All materials, equipment, and workmanship shall be in accordance with applicable sections of the West Virginia Department of Transportation, Division of Highways, Standard Specifications for Roads and Bridges, adopted 2023, and the West Virginia Department of Transportation, Division of Highways Supplemental Specifications dated 2025, including the most recent supplemental specifications and the Standard Details Book, Volume 1, Drainage, Guardrail, Pavement, Fence, and Markers, Issue Date: May, 2016 (WVDOH Standard Details).

<https://transportation.wv.gov/highways/TechnicalSupport/specifications/Pages/default.aspx>

https://transportation.wv.gov/highways/TechnicalSupport/specifications/Documents/2025%20Supplemental%20Specifications_20241209.pdf

<https://transportation.wv.gov/highways/engineering/StandardDetails/Vol1/Std%20Dtls%20Vol%201%202016%20with%20Revisions%20Through%202021-12-9.pdf>

The quantities listed in the contract documents are estimates. The City will pay for quantities actually in place. The City reserves the right to vary the quantities up to 50 % with no change in unit price, except for optional items that may or may not be completed as part of this project.

Contractor shall comply with all applicable laws, ordinances, regulations, and codes of the federal government, State of West Virginia, Kanawha County, and the City of Charleston, West Virginia, applicable to this Agreement and any Services performed hereunder, including but not limited to employment laws, immigration laws and drug free requirements. If Contractor fails to comply with the aforementioned laws and/or requirements, the City may, at its discretion, take appropriate action, including, but not limited to, calling Contractors' bonds and/or terminating this Agreement immediately.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Note: Part or all of the funding for this contract may be provided by federal funds. The vendor must adhere to the attached Federal Funds Addendum, including the Federal Wage Rates requirements.

All persons employed by contractor or subcontractors on this project shall be paid wages at rates not less than those determined by the Secretary of Labor in accordance with the Davis-Bacon Act, as amended (40 U.S.C. 277a-276-c-5), and shall receive overtime compensation in accordance with and subject to the provisions of the Contract Work Hours and Safety Standards Act (40 U.S.C. 27-333), and the contractors and subcontractors shall comply with all regulations issued pursuant to these Acts and with other applicable Federal laws and regulation pertaining to labor standards.

A copy of the Federal Wage Rates is attached. The successful bidder will be required to submit copies of weekly payrolls and, if necessary, submit them to on-site inspections and interviews.

The contractor shall provide a tentative construction schedule. The schedule shall include anticipated start and completion dates, sequence of construction activity and estimated duration of each activity. The construction schedule shall be updated with each invoice.

The project shall be substantially completed within 7 months after the Notice to Proceed is issued.

- 2. DEFINITIONS: THE** terms listed below shall have the meanings assigned to them below. Additional definitions can be found in section 2 of the General Terms and Conditions and in the Project Plans as defined below.

2.1 “Construction Services” installation of concrete sidewalk and accessible ramps as more fully described by these specifications.

2.2 “Pricing Page” means the pages upon which Vendor should list its proposed price for the Construction Services.

2.3 “Solicitation” means the official notice of an opportunity to supply the City of Charleston, WV with goods or services that is published on the City’s website located at <https://charlestonwv.gov/bids-purchasing/current-bids>

- 3. GENERAL REQUIREMENTS:** All specifications are minimum requirements unless otherwise stated. Any deviations from the stated specifications must be described in detail. The merit of such deviations will be considered with regard to the City of Charleston’s intended use.

3.1 MOBILIZATION:

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

3.1.1 DESCRIPTION: This work shall consist of the preparation for construction, movement of personnel, equipment, and materials to the project site. This item will include site preparation, clean-up and demobilization. Mobilization shall not exceed 5% of the Project Total.

3.1.2 MATERIALS & METHODS: This work shall consist of the preparation for construction, movement of personnel, equipment, and materials to the project site. This item will include site preparation, clean-up and demobilization. Mobilization shall not exceed 5% of the Project Total.

3.1.3 MEASUREMENT & PAYMENT: Mobilization will be measured and paid on a lump sum basis for ITEM 3.1 MOBILIZATION. The City will hold a 10% retainment pending final acceptance of the job. No decrease or increases will be made on this item price regardless of the decrease or increase in the final total contract amount or for any other cause.

3.2 TRAFFIC CONTROL:

3.2.1 DESCRIPTION: This work shall consist of furnishing, installing, maintaining and removing necessary devices for control and protection of vehicles, bicyclists and pedestrians. Devices include but are not limited to signage, fencing, cones, barricades, flaggers, temporary traffic signals, etc. The contractor shall prepare a traffic control plan and submit it to the City of Charleston Traffic and Transportation Department for review and approval. The latest version of the MUTCD (Maintenance of Traffic Control Devices) shall define the standards required to install and maintain all traffic control devices.

The contractor shall conduct the work in a manner and sequence to minimize interference with traffic.

It shall be the responsibility of the contractor to contact the area residents prior to construction activity that impedes access to their driveway, parking area, sidewalk, etc.

A minimum of one lane of traffic shall be maintained throughout the project. Temporary traffic signals and/or flaggers shall be used when construction limits Chesterfield Avenue to one lane.

3.2.2 MATERIALS & METHODS: No decrease or increases will be made in the lump sum bid for Item 3.2 TRAFFIC CONTROL regardless of the decrease or increase in the final total Contract amount or for any other cause.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

3.2.3 MEASUREMENT & PAYMENT: There will be no direct measurement of materials, labor or services provided. Traffic Control will be paid on a lump sum basis for ITEM 3.2 TRAFFIC CONTROL. Payment will be made on a percentage of project completed basis.

3.3 EROSION & SEDIMENT CONTROL:

3.3.1 DESCRIPTION: This work shall consist of temporary and permanent measures performed to control erosion and sedimentation from the construction site. Measures may include but are not limited to silt fence, wattles, inlet protection devices, and seeding. These temporary erosion control measures shall continue until permanent controls have been established and the need has been eliminated as determined by the engineer, or the project has been completed and accepted. The contractor is responsible for removing all temporary sediment control devices.

3.3.2 MATERIALS & METHODS: Erosion and Sediment Control measures shall be installed and maintained in accordance with the WV DEP Erosion and Sediment Control BMP Manual. Measures will be considered acceptable when they can accomplish the intended purpose.

E & S controls shall be installed prior to any storm sewer system construction. Controls shall be installed downslope of any disturbed area.

All controls shall be inspected at least once a week and after a ½-in or greater rain event.

Stabilization measures shall be initiated as soon as practical in portions of the site where construction activities have temporarily or permanently ceased. Areas where the seed fails to germinate adequately shall be reseeded.

3.3.3 MEASUREMENT & PAYMENT: Erosion & Sediment Control shall be measured and paid on a lump sum basis. Partial payments will be made on a percentage of project completed basis.

The City will hold a ten percent (10%) retainage pending final acceptance of the job. No decrease or increases will be made to this item price regardless of the decrease or increase in the final total contract amount or for any other cause. Materials, installation, maintenance and other items incidental to item will be measured and paid on a lump sum basis for ITEM 3.3 EROSION AND SEDIMENT CONTROL.

3.4 12-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

3.4.1 DESCRIPTION: This work shall consist of the construction or reconstruction of pipe culverts, in accordance with the WVDOH Standard Specs Roads & Bridges, adopted 2023, and in reasonably close conformity with the lines, grades, dimensions, and locations shown on the plans or established by the engineer.

3.4.2 MATERIALS & METHODS: The material will be 12-inch HDPE corrugated double wall smooth interior pipe, meeting WVDOH requirements, referring to Sections 604 and 714 of the WVDOH Specification. The pipe shall be installed in accordance with the WVDOH Specification and the manufacturer's specifications.

The trench shall be excavated wide enough to place, and compact backfill around the entire pipe, refer to minimum trench width requirement provided on plans. The contractor may reduce the trench width if specified by the manufacturer.

The bedding for any pipe installed in the roadway shall consist of a continuous four (4) inch layer of crushed aggregate shaped to fit the lower pipe exterior and to the plan details. Recesses shall be made to accommodate the bell where necessary. Pipe placement shall begin at the downstream end, unless otherwise directed or approved by the engineer. The lower segment of the pipe shall be in contact with the shaped bedding throughout its full length. Bell ends of pipe shall be placed facing upstream. The pipe end sections shall be such that the pipe inverts are fully entered and reasonably flush and even.

Care shall be taken to compact the material under the haunches of the pipe, #57 aggregate shall be used for any pipe within the roadway. Place the backfill evenly on each side of pipe to retain its vertical axis, and to avoid displacement and/or floating. Voids shall be eliminated by knifing under and around the pipe. Backfill material above the haunches shall be #57 aggregate for any pipe installed in the roadway.

Any lateral pipe connections that are encountered while installing the pipe, removing any existing pipe or removing any inlet shall be reconnected. All materials, labor and equipment to reconnect any existing connections shall be considered incidental.

Prior to construction the contractor shall submit the pipe manufacturer, product specifications and manufacturer installation recommendations.

The storm sewer trench shall be restored as per the appropriate Trench Detail provided on the plans. All materials, labor, equipment and incidentals necessary to complete the road restoration shall be considered incidental unless otherwise noted in the project specifications and plans.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

The contractor is responsible for properly disposing of all waste materials. All soil, asphalt, concrete, rock, debris, old pipe, etc. shall be disposed of off-site. The contractor shall abide by all appropriate regulations and is responsible for obtaining all necessary permits.

3.4.3 MEASUREMENT & PAYMENT: Pipe Culvert shall be measured by the linear feet (LF) in place, the measurement being made along the centerline of pipe installed. The quantities will be paid for at the contract unit price bid for this item, which shall be full compensation for removing any existing pipe that is being replaced, waste material disposal, backfilling, placing 8-inch Class A concrete cap, furnishing all material and doing all work prescribed in a workmanlike and acceptable manner, including all labor, tools equipment, supplies, and incidentals necessary to complete the work. Materials, installation, and other items incidental to item will be measured and paid on a unit basis LINEAR FOOT (LF) for ITEM 3.4 12-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE.

3.5 15-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE:

3.5.1 DESCRIPTION: This work shall consist of the construction or reconstruction of pipe culverts, in accordance with the WVDOH Standard Specs Roads & Bridges, adopted 2023, and in reasonably close conformity with the lines, grades, dimensions, and locations shown on the plans or established by the engineer.

3.5.2 MATERIALS & METHODS: The material will be 15-inch HDPE corrugated double wall smooth interior pipe, meeting WVDOH requirements, refer to Sections 604 and 714 of the WVDOH Specification. The pipe shall be installed in accordance with the WVDOH Specification and the manufacturer's specifications.

The trench shall be excavated wide enough to place, and compact backfill around the entire pipe, refer to minimum trench width requirement provided on plans. The contractor may reduce the trench width if specified by the manufacturer.

The bedding for any pipe installed in the roadway shall consist of a continuous four (4) inch layer of crushed aggregate shaped to fit the lower pipe exterior and to the plan details. Recesses shall be made to accommodate the bell where necessary. Pipe placement shall begin at the downstream end, unless otherwise directed or approved by the engineer. The lower segment of the pipe shall be in contact with the shaped bedding throughout its full length. Bell ends of pipe shall be placed facing upstream. The pipe end sections shall be such that the pipe inverts are fully entered and reasonably flush and even.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Care shall be taken to compact the material under the haunches of the pipe; #57 aggregate shall be used for any pipe within the roadway. Place the backfill evenly on each side of pipe to retain its vertical axis, and to avoid displacement and/or floating. Voids shall be eliminated by knifing under and around the pipe. Backfill material above the haunches shall be #57 aggregate for any pipe installed in the roadway.

Any lateral pipe connections that are encountered while installing the pipe, removing any existing pipe or removing any inlet shall be reconnected. All materials, labor and equipment to reconnect any existing connections shall be considered incidental.

Prior to construction the contractor shall submit the pipe manufacturer, product specifications and manufacturer installation recommendations.

The storm sewer trench shall be restored as per the appropriate Trench Detail provided on the plans. All materials, labor, equipment and incidentals necessary to complete the road restoration shall be considered incidental unless otherwise noted in the project specifications and plans.

The contractor is responsible for properly disposing of all waste materials. All soil, asphalt, concrete, rock, debris, old pipe, etc. shall be disposed of off-site. The contractor shall abide by all appropriate regulations and is responsible for obtaining all necessary permits.

3.5.3 MEASUREMENT & PAYMENT: Pipe Culvert shall be measured by the linear feet (LF) in place, the measurement being made along the centerline of pipe installed. The quantities will be paid for at the contract unit price bid for this item, which shall be full compensation for removing any existing pipe that is being replaced, waste material disposal, backfilling, placing 8-inch Class A concrete cap, furnishing all material and doing all work prescribed in a workmanlike and acceptable manner, including all labor, tools equipment, supplies, and incidentals necessary to complete the work. Materials, installation, and other items incidental to item will be measured and paid on a unit basis LINEAR FOOT (LF) for ITEM 3.5 15-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE.

3.6 18-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE:

3.6.1 DESCRIPTION: This work shall consist of the construction or reconstruction of pipe culverts, in accordance with the WVDOH Standard Specs Roads & Bridges, adopted 2023, and in reasonably close conformity with the lines, grades, dimensions, and locations shown on the plans or established by the engineer.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

3.6.2 MATERIALS & METHODS: The material will be 18-inch HDPE corrugated double wall smooth interior pipe, meeting WVDOH requirements, referring to Sections 604 and 714 of the WVDOH Specification. The pipe shall be installed in accordance with the WVDOH Specification and the manufacturer's specifications.

The trench shall be excavated wide enough to place, and compact backfill around the entire pipe, refer to minimum trench width requirement provided on plans. The contractor may reduce the trench width if specified by the manufacturer.

The bedding for any pipe installed in the roadway shall consist of a continuous four (4) inch layer of crushed aggregate shaped to fit the lower pipe exterior and to the plan details. Recesses shall be made to accommodate the bell where necessary. Pipe placement shall begin at the downstream end, unless otherwise directed or approved by the engineer. The lower segment of the pipe shall be in contact with the shaped bedding throughout its full length. Bell ends of pipe shall be placed facing upstream. The pipe end sections will be such that the pipe inverts are fully entered and reasonably flush and even.

Care shall be taken to compact the material under the haunches of the pipe; #57 aggregate shall be used for any pipe within the roadway. Place the backfill evenly on each side of pipe to retain its vertical axis, and to avoid displacement and/or floating. Voids shall be eliminated by knifing under and around the pipe. Backfill material above the haunches shall be #57 aggregate for any pipe installed in the roadway.

Any lateral pipe connections that are encountered while installing the pipe, removing any existing pipe or removing any inlet shall be reconnected. All materials, labor and equipment to reconnect any existing connections shall be considered incidental.

Prior to construction the contractor shall submit the pipe manufacturer, product specifications and manufacturer installation recommendations.

The storm sewer trench shall be restored as per the appropriate Trench Detail provided on the plans. All materials, labor, equipment and incidentals necessary to complete the road restoration shall be considered incidental unless otherwise noted in the project specifications and plans.

The contractor is responsible for properly disposing of all waste materials. All soil, asphalt, concrete, rock, debris, old pipe, etc. shall be disposed of off-site. The contractor shall abide by all appropriate regulations and is responsible for obtaining all necessary permits.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

3.6.3 MEASUREMENT & PAYMENT: Pipe Culvert shall be measured by the linear feet (LF) in place, the measurement being made along the centerline of pipe installed. The quantities will be paid for at the contract unit price bid for this item, which shall be full compensation for removing any existing pipe that is being replaced, waste material disposal, backfilling, placing 8-inch concrete cap, furnishing all material and doing all work prescribed in a workmanlike and acceptable manner, including all labor, tools equipment, supplies, and incidentals necessary to complete the work. Materials, installation, and other items incidental to item will be measured and paid on a unit basis LINEAR FOOT (LF) for ITEM 3.6 18-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE.

3.7 24-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE:

3.7.1 DESCRIPTION: This work shall consist of the construction or reconstruction of pipe culverts, in accordance with the WVDOH Standard Specs Roads & Bridges, adopted 2023, and in reasonably close conformity with the lines, grades, dimensions, and locations shown on the plans or established by the engineer.

3.7.2 MATERIALS & METHODS: The material will be 24-inch HDPE corrugated double wall smooth interior pipe, meeting WVDOH requirements, refer to Sections 604 and 714 of the WVDOH Specification. The pipe shall be installed in accordance with the WVDOH Specification and the manufacturer's specifications.

The trench shall be excavated wide enough to place, and compact backfill around the entire pipe, refer to minimum trench width requirement provided on plans. The contractor may reduce the trench width if specified by the manufacturer.

The bedding for any pipe installed in the roadway shall consist of a continuous four (4) inch layer of crushed aggregate shaped to fit the lower pipe exterior and to the plan details. Recesses shall be made to accommodate the bell where necessary. Pipe placement shall begin at the downstream end, unless otherwise directed or approved by the engineer. The lower segment of the pipe shall be in contact with the shaped bedding throughout its full length. Bell ends of pipe shall be placed facing upstream. The pipe end sections will be such that the pipe inverts are fully entered and reasonably flush and even.

Care shall be taken to compact the material under the haunches of the pipe; #57 aggregate shall be used for any pipe within the roadway. Place the backfill evenly on each side of pipe to retain its vertical axis, and to avoid displacement and/or floating. Voids shall be eliminated by knifing under and around the pipe. Backfill

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

material above the haunches shall be #57 aggregate for any pipe installed in the roadway.

Any lateral pipe connections that are encountered while installing the pipe, removing any existing pipe or removing any inlet shall be reconnected. All materials, labor and equipment to reconnect any existing connections shall be considered incidental.

Prior to construction the contractor shall submit the pipe manufacturer, product specifications and manufacturer installation recommendations.

The storm sewer trench shall be restored as per the appropriate Trench Detail provided on the plans. All materials, labor, equipment and incidentals necessary to complete the road restoration shall be considered incidental unless otherwise noted in the project specifications and plans.

The contractor is responsible for properly disposing of all waste materials. All soil, asphalt, concrete, rock, debris, old pipe, etc. shall be disposed of off-site. The contractor shall abide by all appropriate regulations and is responsible for obtaining all necessary permits.

3.7.3 MEASUREMENT AND PAYMENT: Pipe Culvert shall be measured by the linear feet (LF) in place, the measurement being made along the centerline of pipe installed. The quantities will be paid for at the contract unit price bid for this item, which shall be full compensation for removing any existing pipe that is being replaced, waste material disposal, backfilling, placing 8-inch concrete cap, furnishing all material and doing all work prescribed in a workmanlike and acceptable manner, including all labor, tools equipment, supplies, and incidentals necessary to complete the work. Materials, installation, and other items incidental to item will be measured and paid on a unit basis LINEAR FOOT (LF) for ITEM 3.07 24-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE.

3.8 30-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE:

3.8.1 DESCRIPTION: This work shall consist of the construction or reconstruction of pipe culverts, in accordance with the WVDOH Standard Specs Roads & Bridges, adopted 2023, and in reasonably close conformity with the lines, grades, dimensions, and locations shown on the plans or established by the engineer.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

3.8.2 MATERIALS & METHODS: The contractor shall remove the existing pipe 30-inch corrugate metal pipe as shown on the plans; the existing trench bottom shall be backfilled with compacted crusher run aggregate to the bottom of the 30-inch HDPE. The contractor shall abandon the existing 30-inch corrugated metal pipe as shown on the plans. The contractor shall plug the 30-inch CMP at the existing manhole and fill 30-in CMP with Controlled Low-Strength Material meeting WVDOH requirement as shown on the plans, refer to Sections 219 of the WVDOH Specification, no material shall enter the manhole.

The material will be 30-inch HDPE corrugated double wall smooth interior pipe, meeting WVDOH requirements, refer to Sections 604 and 714 of the WVDOH Specification. The pipe shall be installed in accordance with the WVDOH Specification and the manufacturer's specifications.

The trench shall be excavated wide enough to place, and compact backfill around the entire pipe, refer to minimum trench width requirement provided on plans. The contractor may reduce the trench width if specified by the manufacturer.

The bedding shall consist of a continuous four (4) inch layer of crushed aggregate shaped to fit the lower pipe exterior and to the plan details. Recesses shall be made to accommodate the bell where necessary. Pipe placement shall begin at the downstream end, unless otherwise directed or approved by the engineer. The lower segment of the pipe shall be in contact with the shaped bedding throughout its full length. Bell ends of pipe shall be placed facing upstream. The pipe end sections shall be such that the pipe inverts are fully entered and reasonably flush and even.

Care shall be taken to compact the material under the haunches of the pipe; #57 aggregate shall be used for any pipe within the roadway. Place the backfill evenly on each side of pipe to retain its vertical axis, and to avoid displacement and/or floating. Voids shall be eliminated by knifing under and around the pipe. Backfill material above the haunches shall be #57 aggregate for any pipe installed in the roadway.

Any lateral pipe connections that were encountered while removing any existing pipe shall be reconnected. All materials, labor and equipment to reconnect any existing connections shall be considered incidental.

Prior to construction the contractor shall submit the pipe manufacturer, product specifications and manufacturer installation recommendations.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

The storm sewer trench shall be restored as per the appropriate Trench Detail provided on the plans. All materials, labor, equipment and incidentals necessary to complete the road restoration shall be considered incidental unless otherwise noted in the project specifications and plans.

The contractor is responsible for properly disposing of all waste materials. All soil, asphalt, concrete, rock, debris, old pipe, etc. shall be disposed of off-site. The contractor shall abide by all appropriate regulations and is responsible for obtaining all necessary permits.

3.8.3 MEASUREMENT AND PAYMENT: Pipe Culvert shall be measured by the linear feet (LF) in place, the measurement being made along the centerline of pipe installed. The quantities will be paid for at the contract unit price bid for this item, which shall be full compensation for removing any existing pipe that is being replaced, abandoning existing 30-in CMP with CLSM, plugging the existing 30-in CMP to existing manhole connection, waste material disposal, backfilling, connecting all laterals, furnishing all material and doing all work prescribed in a workmanlike and acceptable manner, including all labor, tools equipment, supplies, and incidentals necessary to complete the work. Materials, installation, and other items incidental to item will be measured and paid on a unit basis LINEAR FOOT (LF) for ITEM 3.8 30-INCH CORRUGATED HIGH DENSITY POLYETHYLENE PIPE.

3.9 4' DIAMETER MANHOLE:

3.9.1 DESCRIPTION: This work shall consist of the construction of new 4-foot diameter manhole in accordance with the WVDOH Standard Specs Roads & Bridges, adopted 2023, and in reasonably close conformity with the lines, grades, dimensions and locations shown on the plans or established by the engineer.

3.9.2 MATERIAL & METHODS: Manholes shall meet the requirements of Section 605 of the WVDOH Specifications.

Concrete manholes shall be precast with shapes and dimensions that conform to those shown on the plans unless otherwise directed by the engineer. The final installed top surfaces are to be flush with adjacent finish surfaces such as pavement, gutters and/or curbs. Portland cement concrete or a high strength, non-shrink grout shall form neatly and tightly around all pipes connecting to the manhole.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Crushed granular material meeting the requirements of #57, 76 or 78 sizes shall be used for the foundation. The foundation shall be a minimum of 6 inches thick and extend 4 inches outside the manhole base.

Manhole frames and grates shall be gray iron castings from a WVDOH approved source.

Precast manholes shall be from an approved Precast Concrete Fabricator. Prior to construction the contractor shall submit the following information for precast structures, frames and grates as applicable: Fabricator, product specifications and/or manufacturer installation instructions.

The asphalt or concrete around the inlet shall be saw-cut and restored as per the appropriate Standard Detail in the Appendix. The street restoration is considered incidental.

3.9.3 MEASUREMENT & PAYMENT: Manholes will be measured by the units in place. The quantities will be paid for at the contract unit price bid for this item, which shall be full compensation for backfilling, concrete, aggregate, reinforcing steel, grates, covers, frames, hardware, and other material required to install and for doing all work, including all labor, tools equipment, supplies, and incidentals necessary to complete the work. Materials, installation, and other items incidental to item will be measured and paid on a unit basis EACH (EA) for ITEM 3.9 4-FOOT DIAMETER MANHOLE.

3.10 5' DIAMETER MANHOLE:

3.10.1 DESCRIPTION: This work shall consist of the construction of new 5-foot Diameter Manhole in accordance with the WVDOH Standard Specs Roads & Bridges, adopted 2023, and in reasonably close conformity with the lines, grades, dimensions and locations shown on the plans or established by the engineer.

3.10.2 MATERIAL & METHODS: Manholes shall meet the requirements of Section 605 of the WVDOH Specifications.

Concrete manholes shall be precast with shapes and dimensions that conform to those shown on the plans unless otherwise directed by the engineer. The final installed top surfaces are to be flush with adjacent finish surfaces such as pavement, gutters and/or curbs. Portland cement concrete or a high strength, non-shrink grout shall form neatly and tightly around all pipes connecting to the manhole.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Crushed granular material meeting the requirements of #57, 76 or 78 size shall be used for the foundation. The foundation shall be a minimum of 6 inches thick and extend 4 inches outside the manhole base.

Manhole frames and grates shall be gray iron castings from a WVDOH approved source.

Precast manholes shall be from an approved Precast Concrete Fabricator. Prior to construction the contractor shall submit the following information for precast structures, frames and grates as applicable: Fabricator, product specifications and/or manufacturer installation instructions.

The asphalt or concrete around the inlet shall be saw-cut and restored as per the appropriate Standard Detail in the Appendix.

3.10.3 MEASUREMENT & PAYMENT:

Manholes will be measured by the units in place. The quantities will be paid for at the contract unit price bid for this item, which shall be full compensation for backfilling, concrete, aggregate, reinforcing steel, grates, covers, frames, hardware, and other material shown on the plans and for doing all work, including all labor, tools equipment, supplies, and incidentals necessary to complete the work. Materials, installation, and other items incidental to item will be measured and paid on a unit basis EACH (EA) for ITEM 3.10 5-FOOT DIAMETER MANHOLE INLET.

3.11 TYPE-G DRAIN INLETS:

3.11.1 DESCRIPTION: This work shall consist of the construction of new Type-G inlets in accordance with the WVDOH Standard Specs Roads & Bridges, adopted 2023, and in reasonably close conformity with the lines, grades, dimensions and locations shown on the plans or established by the engineer.

3.11.2 MATERIAL & METHODS: Concrete inlets shall be fabricated to conform to the alignment and elevation shown on the plans unless otherwise directed by the engineer.

Crushed granular material meeting the requirements of #57, 76 or 78 size shall be used for the foundation. The foundation shall be a minimum of 6 inches thick and extend 4 inches outside the inlet base.

Portland cement concrete or a high strength, non-shrink grout shall form neatly and tightly around all pipes connecting to the inlet. Inlets shall be constructed in a manner that prevents infiltration.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Inlet frames and grates shall be structural steel meeting Section 709.12 of the WVDOH Specifications. Bicycle safe grates shall be installed.

Precast inlets shall be from an approved Precast Concrete Fabricator. Prior to construction the contractor shall submit the following information for precast structures, frames and grates as applicable: Fabricator, product specifications and/or manufacturer installation instructions.

The asphalt or concrete around the inlet shall be saw-cut and restored as per the appropriate Standard Detail in the Appendix. The street restoration is considered incidental.

3.11.03 MEASUREMENT & PAYMENT: Inlets will be measured by the units in place. The quantities will be paid for at the contract unit price bid for this item, which shall be full compensation for backfilling, concrete, aggregate, reinforcing steel, grates, covers, frames, hardware, and other material shown on the plans and for doing all work, including all labor, tools equipment, supplies, and incidentals necessary to complete the work. Materials, installation, and other items incidental to item will be measured and paid on a unit basis EACH (EA) for ITEM 3.11 TYPE-G DRAIN INLET.

3.12 TYPE-B DRAIN INLETS:

3.12.1 DESCRIPTION: This work shall consist of the construction of new Type-B inlets in accordance with the WVDOH Standard Specs Roads & Bridges, adopted 2023, and in reasonably close conformity with the lines, grades, dimensions and locations shown on the plans or established by the engineer.

3.12.2 MATERIAL & METHODS: Concrete inlets shall be fabricated to conform to the alignment and elevation shown on the plans unless otherwise directed by the engineer.

Crushed granular material meeting the requirements of #57, 76 or 78 size shall be used for the foundation. The foundation shall be a minimum of 6 inches thick and extend 4 inches outside the inlet base.

Portland cement concrete or a high strength, non-shrink grout shall form neatly and tightly around all pipes connecting to the inlet. Inlets shall be constructed in a manner that prevents infiltration.

Inlet frames and grates shall be gray iron casting from a WVDOH approved source. Bicycle safe grates shall be installed.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Precast inlets shall be from an approved Precast Concrete Fabricator. Prior to construction the contractor shall submit the following information for precast structures, frames and grates as applicable: Fabricator, product specifications and/or manufacturer installation instructions.

The asphalt or concrete around the inlet shall be saw-cut and restored as per the appropriate Standard Detail in the Appendix. The street restoration is considered incidental.

An 8-inch or 12-inch SDR35 tap shall be installed in inlet as shown on plans. The tap shall extend 1 foot with a cap on the end. Material and installation shall be considered incidental.

3.12.3 MEASUREMENT & PAYMENT: Inlets will be measured by the units in place. The quantities will be paid for at the contract unit price bid for this item, which shall be full compensation for backfilling, concrete, aggregate, reinforcing steel, grates, covers, frames, hardware, and other material shown on the plans and for doing all work, including all labor, tools equipment, supplies, and incidentals necessary to complete the work. Materials, installation, and other items incidental to item will be measured and paid on a unit basis EACH (EA) for ITEM 3.12 TYPE-B DRAIN INLET.

3.13 CLASS K PORTLAND CEMENT CONCRETE PAVEMENT:

3.13.1 DESCRIPTION: This work shall consist of providing all labor, materials, equipment and incidentals required for placement of WVDOT Class K Reinforced Portland Concrete Pavement.

3.13.2 MATERIALS & METHODS: This work shall consist of placement of pavement composed of WVDOT Class K Portland cement concrete with 6x6- 6-gauge wire fabric, coated 1" load transfer dowel bars constructed on a prepared 6" aggregate base course and in reasonably close conformity with the existing lines and grades of the pavement to be replaced. All concrete thicknesses shall be 8" unless directed by the Engineer.

The new concrete should be finished with the surface to approximately match the existing adjacent panels.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Refer to SECTIONS 501, 506 and 601 of the most current West Virginia Department of Transportation, Division of Highways Standard Specifications, Roads and Bridges.

All concrete shall be in accordance with the WVDOH STANDARD SPECIFICATIONS SECTION 501 and 506, unless otherwise specified in the plans.

Incidental work to be included with item 3.13 (but not limited to) is detailed below.

3.13.2.1 DEMOLITION AND DISPOSAL OF DAMAGED CONCRETE PAVEMENT: Existing concrete pavement to be replaced should be completely removed by the contractor and disposed of properly.

3.13.2.2 PREPARE SUBGRADE: Prepared subgrade shall generally meet the compaction requirements of 95% by volume. The contractor should perform adequate compaction testing to assure that differential settlement of the finished concrete panel will not take place to an extent that the panel fails to provide a smooth travel surface (i.e. joint displacement). Panels which settle below the grade of adjacent panels to an extent that a noticeable bump is encountered by the traveling public shall be removed and replaced at the expense of the contractor. Subgrade preparation shall be in accordance with WVDOH STANDARD SPECIFICATIONS SECTION 228.

3.13.2.3 SAW-CUTTING EXISTING CONCRETE: The contractor shall cut the existing concrete in straight lines as directed by the engineer.

3.13.2.4 COATED DOWEL BARS AND TIEBARS: Coated dowel bars meeting Section 709.15 of the WVDOT Standard Specifications, Roads and Bridges, shall be used to transmit load. These should be located at or near the center of the pavement thickness, and should be 1' diameter coated dowel bars, 12" long, placed at 24" on center. Dowels should be lubricated and misalignment held to a minimum.

Coated dowel bars are to be placed at all transverse joints unless otherwise directed by the Engineer, the contractor shall stage concrete pours to allow placement of dowel bars or Load Transfer Units shall be installed.

Tie bars are to be placed at longitudinal joints as per attached details or as directed by the Engineers. Tie bars are to be deformed #4 bar at 30" inch spacing unless otherwise directed by the Engineer.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

3.13.2.5 EXPANSION AND ISOLATION JOINT MATERIAL:

Isolation joints shall be used to separate concrete from fixed objects such as manholes, inlets, sidewalks, foundations, etc. The following material shall be used unless otherwise directed by the Engineer: Self-expanding cork ASTM D 1752, Type III, Neoprene/SBR Polymer conforming to ASTM D 1056-67 or Cellular fiber-asphalt conforming to ASTM D 1751.

3.13.2.6 AGGREGATE: The Contractor shall place aggregate base course on prepared subgrade as per Section 307 CRUSHED AGGREGATE BASE COURSE of the most current WVDOH Standard Specifications. Compact aggregate base course at 95% maximum density in accordance with ASTM 1557

3.13.3 MEASUREMENT & PAYMENT: Class K Portland Cement Concrete Pavement includes concrete placed as final driving and parking surface, refer to plans for locations. Materials, installation, and other items incidental to item will be measured and paid on a unit basis SQUARE YARD for ITEM 3.13 CLASS K PORTLAND CEMENT CONCRETE PAVEMENT.

4. **CONTRACT AWARD:** The Contract is intended to provide the City with a purchase price for the Construction Services. The Contract will be awarded to the lowest qualified responsible bidder meeting the required specifications. If the Pricing Pages contain alternates/add-ons, the Contract will be awarded based on the grand total of the base bid and any alternates/add-ons selected.
5. **SELECTION OF ALTERNATES: PURSUANT** to W. Va. Code § 5-22-1(f), any solicitation of bids shall include no more than five alternates. Alternates, if accepted, shall be accepted in the order in which they are listed on the bid form. Any unaccepted alternate contained within a bid shall expire 90 days after the date of the opening of bids for review. Determination of the lowest qualified responsible bidder shall be based on the sum of the base bid and any alternatives accepted.
6. **PERFORMANCE:** Vendor shall perform the Construction Services in accordance with this document and the Project Plans.
7. **SUBSTITUTIONS:** Any substitution requests must be submitted in accordance with the official question and answer period described in the INSTRUCTIONS TO VENDORS SUBMITTING BIDS, Paragraph 3. Vendor Question Deadline. Vendors submitting substitution requests should submit product brochures and product specifications during the official question and answer period.
8. **PROJECT PLANS:** The checked box will apply to Project Plans for this solicitation.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

- x **No Additional Project Plan Documents:** There are no additional Project Plans other than those attached hereto as an Exhibit or as any subsequent addenda.

Additional Project Plan Documents: There are additional Project Plan documents other than those attached as Exhibit B. Copies of the additional Project Plan documents not attached as Exhibit B can be obtained by contacting the entity identified below.

9. CONDITIONS OF THE WORK

- 9.1. Permits:** The Vendor shall obtain all necessary permits and licenses to comply with all applicable Federal, State, or Local laws, regulations and ordinances of any regulating body.
- 9.2. Existing Conditions:** If discrepancies are discovered between the existing conditions and those noted in the specifications, Vendor must immediately notify the City's representative. Vendor must also immediately notify the City if suspected hazardous materials are encountered.
- 9.3. Standard Work Hours:** The standard hours of work for this Contract will be Monday through Friday, 8am to 5pm EST excluding holidays recognized by the City of Charleston. Any work outside of the standard hours of work must be approved in advance at the City's sole discretion. Authorization of work outside of the standard hours of work will not entitle Vendor to additional compensation.
- 9.4. Project Closeout:** Project Closeout shall include the following:
- 9.4.1 Final Cleanup:** It shall be the responsibility of the vendor to always keep the construction area clean from trash and debris. Vendor shall take measures to protect all utility and manhole lids from concrete splatter during each pour ensuring future accessibility. The final cleanup shall be reviewed by the City Engineer prior to final payment.
- 9.4.1. Final Inspection:** Vendor shall participate in a final inspection with the City's project manager. The purpose of the final inspection will be to identify deficiencies that need to be remedied prior to the City's final acceptance of the work. Vendor shall always be obligated to perform in accordance with the Contract and must take all actions necessary to ensure that work complies with requirements of Contract prior to final acceptance. Final acceptance does not waive or release Vendor from its obligation to ensure that work complies with the Contract requirements. Vendor shall submit any warranty documents to the City project manager at final inspection.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

10. FACILITIES ACCESS: Performance of Contract Services may require access cards and/or keys to gain entrance to the City's facilities. If access cards and/or keys are required:

10.1. Vendor must identify principal service personnel which will be issued access cards and/or keys to perform service.

10.2. Vendor will be responsible for controlling cards and keys and will pay replacement fee, if the cards or keys become lost or stolen.

10.3. Vendor shall notify the City immediately of any lost, stolen, or missing card or key.

10.4. Anyone performing under this Contract will be subject to the City's security protocol and procedures.

10.5. Vendor shall inform all staff of City's security protocol and procedures.

11. MISCELLANEOUS:

11.1. Contract Manager: During its performance of this Contract, Vendor must designate and maintain a primary contract manager responsible for overseeing Vendor's responsibilities under this Contract. The Contract manager must be available during normal business hours to address any customer service or other issues related to this Contract. Vendor should list its Contract manager and his or her contact information below.

Contract Manager: _____

Telephone Number: _____

Fax Number: _____

Email Address: _____

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

PROPOSED EXCEPTIONS AND DEVIATIONS

Bidder shall fully describe every variance, exception and/or deviation. Please include with your pricing page. Additional sheets may be used if required.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Pricing Page

We agree to sell and perform for the City of Charleston the above project as described in the attached specifications for the price listed below:

Description	Unit	Quantity	Unit Cost	Item Total
Item 3.1 Mobilization (5% Max.)	LS	1		
Item 3.2 Traffic Control	LS	1		
Item 3.3 Erosion and Sediment Control	LS	1		
Item 3.4 12-inch Corrugated High Density Polyethylene Pipe	LF	210		
Item 3.5 15-inch Corrugated High Density Polyethylene Pipe	LF	360		
Item 3.6 18-inch Corrugated High Density Polyethylene Pipe	LF	825		
Item 3.7 24-inch Corrugated High Density Polyethylene Pipe	LF	50		
Item 3.8 30-inch Corrugated High Density Polyethylene Pipe	LF	160		
Item 3.9 4' Diameter Manhole	EA	1		
Item 3.10 5' Diameter Manhole	EA	2		
Item 3.11 Type-G Drain Inlet	EA	5		
Item 3.12 Type-B Drain Inlet	EA	14		
Item 3.13 Class K Portland Cement Concrete Pavement	SY	250		
			BID TOTAL	

All items required for project completion but not listed separately shall be considered incidental to the items shown. Quantities are estimates for bidding purposes only; the City of Charleston will only pay for actual quantities installed.

REQUEST FOR QUOTATION
2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

PROJECT PLANS

Project Plans Begin on Next Page

THE UTILITY LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATE, THE CONTRACTOR SHALL LOCATE AND PROTECT THE EXISTING UTILITIES. THE CONTRACTOR SHALL CONTACT ALL UTILITY AGENCIES FOR FIELD MARKING PRIOR TO BEGINNING CONSTRUCTION.

ALL BROKEN ASPHALT & CONCRETE, SOIL, AGGREGATE, TRASH, ETC. SHALL BE DISPOSED OF OFF-SITE BY THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FOR OFF-SITE DISPOSAL/WASTE AREAS.

ANY CONSTRUCTION METHOD OR MATERIAL THAT IS NOT COVERED IN THE CONTRACT SPECIFICATIONS WILL BE COVERED BY THE WVDOT, DIVISION OF HIGHWAYS STANDARD SPECIFICATIONS ROADS AND BRIDGES ADOPTED 2023 AND THE WVDOT, DIVISION OF HIGHWAYS SUPPLEMENTAL SPECIFICATIONS DATED 2025, STANDARD DETAILS VOLUME 1 DATED MAY 2016 WITH REVISIONS THROUGH DECEMBER 2021.

TRENCH SAFETY- THE CONTRACTOR SHALL TAKE APPROPRIATE MEASURE TO ENSURE SAFETY OF PERSONNEL AND PUBLIC, PROTECT WORK, AND ADJACENT ROADWAY.

THE CONTRACTOR SHALL CONTACT MT. GAS TO RELOCATE ANY MAIN GAS LINES OR GAS LATERALS THAT CONFLICT WITH STORM SEWER PLACEMENT. CONTRACTOR IS NOT RESPONSIBLE FOR RELOCATION COST.

BICYCLE SAFE GRATES SHALL BE USED.

This diagram illustrates the trench patching method for a trench repair. The cross-section shows a trench cut into the existing pavement. The repair consists of several layers: a 4-inch bedding layer at the bottom, trench backfill (represented by a pebbled pattern) on top of the bedding, and a Class 'A' concrete cap on top of the backfill. The concrete cap is 8 inches thick. The trench is 9 inches wide, with a minimum width indicated. The existing concrete/asphalt is shown on the left and right sides of the trench. Labels indicate the following components and dimensions:

- Existing Asphalt Overlay (Match existing edge of road where applicable. Place Topsoil to disturbed grass area)
- Sawcut Through Asphalt And Concrete
- Existing Concrete/Asphalt
- Class 'A' Concrete Cap
- 8" (thickness of concrete cap)
- 9" Min. (trench width)
- Trench Backfill
- 4-in Bedding
- Min. Trench Width
- Fill Both Sides of Pipe Simultaneously. Work Material Around Pipe to Eliminate Voids
- Sawcut Through Asphalt And Concrete

Match existing edge of pavement where applicable

Minimum Trench Width	
Pipe Dia.	Min trench Width
12-inch	31 inches
15-inch	34 inches
18-inch	39 inches
24-inch	47 inches
30-inch	56 inches

Diagram illustrating the cross-section of a trench repair. The diagram shows a trench with a circular pipe at the bottom. The layers and materials are labeled as follows:

- Existing Asphalt Overlay**: The top layer on the left, with a note: "(Match existing edge of road where applicable. Place Topsoil to disturbed grass area)".
- Leave Concrete 15" Below Adjacent Asphalt**: A note pointing to the top of the concrete cap.
- Repair Grass/Stone To Pre-Construction Condition**: A note pointing to the stone area on the right.
- Existing Concrete/Asphalt**: The layer on the left, with a 5' dimension.
- Class 'A' Concrete Cap**: The top layer of the trench, with a 9' dimension.
- Trench Backfill**: The material filling the trench, with a 9' dimension.
- 4-in Bedding**: The layer at the bottom of the trench, with a 4-in dimension.
- Min. Trench Width**: The width of the trench at the bottom.
- Fill Both Sides of Pipe Simultaneously. Work Material Around Pipe to Eliminate Voids**: A note pointing to the backfill material around the pipe.

Match existing edge of pavement where applicable

Minimum Trench Width	
Pipe Dia.	Min trench Width
12-inch	31 inches
15-inch	34 inches
18-inch	39 inches
24-inch	47 inches
30-inch	56 inches

Diagram illustrating the construction of a trench repair, showing the following components and materials:

- Class K Concrete (Paid Item 3.13)
- 12"-#4 Coated Dowels • 24" O.C.
- Sawcut Through Concrete (Match existing edge of road where applicable. Place Topsoil to disturbed grass area)
- Existing Concrete
- Class "K" Concrete
- Existing Concrete
- 3-in Aggregate Base
- 9" (Min.)
- 9" (Min.)
- Trench Backfill
- 4-in Bedding
- Min. Trench Width
- Fill Both Sides of Pipe Simultaneously. Work Material Around Pipe to Eliminate Voids

Use 1/2" dia. epoxy coated dowel, 12' long, 24" on-center if existing concrete street is 6" thick or greater.
or greater.

Minimum Trench Width	
Pipe Dia.	Min trench Width
12-inch	31 inches
15-inch	34 inches
18-inch	39 inches
24-inch	47 inches
30-inch	56 inches

ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL MEET WVDEP MANUAL REQUIREMENTS. DEVICES SHALL BE INSTALLED AND MAINTAINED AS PER WV DEP MANUAL AND/OR THE CITY OF CHARLESTON STORMWATER MANUAL.

PRIOR TO ANY CONSTRUCTION, INLET PROTECTION SHALL BE INSTALLED ON ALL INLETS THAT COULD RECEIVE WATER FROM A DISTURBED AREA. INLETS INSTALLED IN DRIVING AREAS SHALL HAVE MANUFACTURED DROP INLET PROTECTION INSTALLED.

IMMEDIATELY SEED DISTURBED AFTER FINISH GRADING IS COMPLETE. AREA WHERE THE SEED FAILS TO GERMINATE ADEQUATELY (UNIFORM COVER WITH A DENSITY OF 70%) SHALL BE RESEEDDED.

SEDIMENT BARRIERS SHALL REMAIN UNTIL VEGETATION IS ESTABLISHED AND AREA IS STABILIZED.

ALL DEVICES SHALL BE INSPECTED AT LEAST ONCE A WEEK AND AFTER EACH RAIN EVENT OF 0.5-in OR GREATER. SEDIMENT ACCUMULATIONS THAT ARE GREATER THAN 1/2 THE HEIGHT OF THE WATTLE OR SIX (6) INCHES ABOVE THE BASE OF THE SILT FENCE SHALL BE REMOVED.

LAWN AREAS: REMOVE ROCKS AND DEBRIS, LOOSEN THE SOIL, ADD TOPSOIL IF NEEDED, ADD FERTILIZER AND RAKE TO PRODUCE A UNIFORM WELL GRADED SURFACE, LOOSEN THE SOIL PRIOR TO APPLYING THE SEED. ALL LAWN AREAS SHALL BE SEEDED WITH TALL FESCUE SEED UNLESS OTHERWISE DIRECTED BY THE CITY.

1-inch Coated Dowel Bar
WDOH 709.15

Existing Concrete Roadway

New Concrete Roadway

#4 Tie Bars
c-c 30"

8-inch Concrete

6-inch Aggregate

6x6-6 Ga. WWF

Engineering Fabric
WDOH 715.11.9

1. Concrete shall be composed of WDOT Class K Concrete
2. Care shall be taken to avoid damage to the existing roadway surface during construction
3. Compact aggregate base course at 95% maximum density

6-7"

6-7"

Class 'K' Concrete

6"

6"

Engineering Fabric
WVDON 715.11.9

1. Match existing parking area dimensions
2. Concrete shall be composed of WVDOT Class K Concrete
3. Compact aggregate base course, 95% maximum density

NO.	REVISION	DATE

CHESTERFIELD AVE.
HAZARD MITIGATION GRANT
LPDM-PJ-03-WV-2023-0010

PLAN


Scale: N.T.S


**CITY
OF
CHARLESTON
ENGINEERING
DEPARTMENT**




DRAWING NO.

3





NO.	REVISION	DATE
PROJECT TITLE		
CHESTERFIELD AVE. HAZARD MITIGATION GRANT LPDM-PJ-03-WV-2023-0010		
DRAWING TITLE		
PLAN		
Scale: 1"=20'-0"		
CITY OF CHARLESTON ENGINEERING DEPARTMENT		DRAWING NO.
		1

FEDERAL FUNDS ADDENDUM

REQUIRED CONTRACT PROVISIONS FOR NON-FEDERAL ENTITY CONTRACTS UNDER FEDERAL AWARDS (2 C.F.R. § 200.317):

The City of Charleston, WV and the Vendor awarded this Contract intend that this Contract be compliant with the requirements of the Procurement Standards contained in the Uniform Administrative Requirements, Cost Principles, and Audit Requirements found in 2 C.F.R. § 200.317, et seq. for procurements conducted by a Non-Federal Entity. Accordingly, the Parties agree that the following provisions are included in the Contract.

1. MINORITY BUSINESSES, WOMEN'S BUSINESS ENTERPRISES, AND LABOR SURPLUS AREA FIRMS: (2 C.F.R. § 200.321)

- a. The City confirms that it has taken all necessary affirmative steps to assure that minority businesses, women's business enterprises, and labor surplus area firms are used when possible. Those affirmative steps include:
 - (1) Placing qualified small and minority businesses and women's business enterprises on solicitation lists;
 - (2) Assuring that small and minority businesses, and women's business enterprises are solicited whenever they are potential sources;
 - (3) Dividing total requirements, when economically feasible, into smaller tasks or quantities to permit maximum participation by small and minority businesses, and women's business enterprises;
 - (4) Establishing delivery schedules, where the requirement permits, which encourage participation by small and minority businesses, and women's business enterprises;
 - (5) Using the services and assistance, as appropriate, of such organizations as the Small Business Administration and the Minority Business Development Agency of the Department of Commerce; and
 - (6) Requiring the prime contractor, if subcontracts are to be let, to take the affirmative steps listed in paragraphs (1) through (5) above.
- b. Vendor confirms that if it utilizes subcontractors, it will take the same affirmative steps to assure that minority businesses, women's business enterprises, and labor surplus area firms are used when possible.

2. DOMESTIC PREFERENCES: (2 C.F.R. § 200.322)

- a. The City confirms that as appropriate and to the extent consistent with law, it has, to the greatest extent practicable under a Federal award, provided a preference for the purchase, acquisition, or use of goods, products, or materials produced in the United

States (including but not limited to iron, aluminum, steel, cement, and other manufactured products).

b. Vendor confirms that will include the requirements of this Section 2. Domestic Preference in all subawards including all contracts and purchase orders for work or products under this award.

c. Definitions: For purposes of this section:

(1) “Produced in the United States” means, for iron and steel products, that all manufacturing processes, from the initial melting stage through the application of coatings, occurred in the United States.

(2) “Manufactured products” means items and construction materials composed in whole or in part of non-ferrous metals such as aluminum; plastics and polymer-based products such as polyvinyl chloride pipe; aggregates such as concrete; glass, including optical fiber; and lumber.

3. BREACH OF CONTRACT REMEDIES AND PENALTIES:

(2 C.F.R. § 200.327 and Appendix II)

(a) The provisions of West Virginia Code of State Rules § 148-1-5 provide for breach of contract remedies, and penalties. .

4. TERMINATION FOR CAUSE AND CONVENIENCE:

(2 C.F.R. § 200.327 and Appendix II)

(a) The provisions of West Virginia Code of State Rules § 148-1-5 govern Contract termination.

5. EQUAL EMPLOYMENT OPPORTUNITY:

(2 C.F.R. § 200.327 and Appendix II)

Except as otherwise provided under 41 CFR Part 60, and if this contract meets the definition of “federally assisted construction contract” in 41 CFR Part 60–1.3, this contract includes the equal opportunity clause provided under 41 CFR 60–1.4(b), in accordance with Executive Order 11246, “Equal Employment Opportunity” (30 FR 12319, 12935, 3 CFR Part, 1964–1965 Comp., p. 339), as amended by Executive Order 11375, “Amending Executive Order 11246 Relating to Equal Employment Opportunity,” and implementing regulations at 41 CFR part 60, “Office of Federal Contract Compliance Programs, Equal Employment Opportunity, Department of Labor.”

6. DAVIS-BACON WAGE RATES:
(2 C.F.R. § 200.327 and Appendix II)

Vendor agrees that if this Contract includes construction, all construction work in excess of \$2,000 will be completed and paid for in compliance with the Davis–Bacon Act (40 U.S.C. 3141–3144, and 3146–3148) as supplemented by Department of Labor regulations (29 CFR Part 5, “Labor Standards Provisions Applicable to Contracts Covering Federally Financed and Assisted Construction”). In accordance with the statute, contractors must:

- (a) pay wages to laborers and mechanics at a rate not less than the prevailing wages specified in a wage determination made by the Secretary of Labor.
- (b) pay wages not less than once a week.

A copy of the current prevailing wage determination issued by the Department of Labor is attached hereto as Exhibit B. The decision to award a contract or subcontract is conditioned upon the acceptance of the wage determination. The City will report all suspected or reported violations to the Federal awarding agency.

7. ANTI-KICKBACK ACT:
(2 C.F.R. § 200.327 and Appendix II)

Vendor agrees that it will comply with the Copeland Anti-Kick Back Act (40 U.S.C. 3145), as supplemented by Department of Labor regulations (29 CFR Part 3, “Contractors and Subcontractors on Public Building or Public Work Financed in Whole or in Part by Loans or Grants from the United States”). Accordingly, Vendor, Subcontractors, and anyone performing under this contract are prohibited from inducing, by any means, any person employed in the construction, completion, or repair of public work, to give up any part of the compensation to which he or she is otherwise entitled. The City must report all suspected or reported violations to the Federal awarding agency.

8. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT
(2 C.F.R. § 200.327 and Appendix II)

Where applicable, and only for contracts awarded by the City in excess of \$100,000 that involve the employment of mechanics or laborers, Vendor agrees to comply with 40 U.S.C. 3702 and 3704, as supplemented by Department of Labor regulations (29 CFR Part 5). Under 40 U.S.C. 3702 of the Act, Vendor is required to compute the wages of every mechanic and laborer on the basis of a standard work week of 40 hours. Work in excess of the standard work week is permissible provided that the worker is compensated at a rate of not less than one and a half times the basic rate of pay for all hours worked in excess of 40 hours in the work week. The requirements of 40 U.S.C. 3704 are applicable to construction work and provide that no laborer or mechanic must be required to work in surroundings or under working conditions which are unsanitary, hazardous or dangerous. These requirements do not apply to the purchases of supplies or materials or articles ordinarily available on the open market, or contracts for transportation or transmission of intelligence.

9. RIGHTS TO INVENTIONS MADE UNDER A CONTRACT OR AGREEMENT.

(2 C.F.R. § 200.327 and Appendix II)

If the Federal award meets the definition of “funding agreement” under 37 CFR § 401.2 (a) and the recipient or subrecipient wishes to enter into a contract with a small business firm or nonprofit organization regarding the substitution of parties, assignment or performance of experimental, developmental, or research work under that “funding agreement,” the recipient or subrecipient must comply with the requirements of 37 CFR Part 401, “Rights to Inventions Made by Nonprofit Organizations and Small Business Firms Under Government Grants, Contracts and Cooperative Agreements,” and any implementing regulations issued by the awarding agency.

10. CLEAN AIR ACT

(2 C.F.R. § 200.327 and Appendix II)

Vendor agrees that if this contract exceeds \$150,000, Vendor is to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act (42 U.S.C. 7401–7671q) and the Federal Water Pollution Control Act as amended (33 U.S.C. 1251–1387). Violations must be reported to the Federal awarding agency and the Regional Office of the Environmental Protection Agency (EPA).

11. DEBARMENT AND SUSPENSION

(2 C.F.R. § 200.327 and Appendix II)

The City will not award to any vendor that is listed on the government wide exclusions in the System for Award Management (SAM), in accordance with the OMB guidelines at 2 CFR 180 that implement Executive Orders 12549 (3 CFR part 1986 Comp., p. 189) and 12689 (3 CFR part 1989 Comp., p. 235), “Debarment and Suspension.” SAM Exclusions contains the names of parties debarred, suspended, or otherwise excluded by agencies, as well as parties declared ineligible under statutory or regulatory authority other than Executive Order 12549.

12. BYRD ANTI-LOBBYING AMENDMENT

(2 C.F.R. § 200.327 and Appendix II)

Vendors that apply or bid for an award exceeding \$100,000 must file the required certification. Each tier certifies to the tier above that it will not and has not used Federal appropriated funds to pay any person or organization for influencing or attempting to influence an officer or employee of any agency, a member of Congress, officer or employee of Congress, or an employee of a member of Congress in connection with obtaining any Federal contract, grant or any other award covered by 31 U.S.C. 1352. Each tier must also disclose any lobbying with non-Federal funds that takes place in connection with obtaining any Federal award. Such disclosures are forwarded from tier to tier up to the non-Federal award.

13. PROCUREMENT OF RECOVERED MATERIALS

(2 C.F.R. § 200.327 and Appendix II; 2 C.F.R. § 200.323)

Vendor agrees that it and the City must comply with section 6002 of the Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act. The requirements of Section 6002 include procuring only items designated in guidelines of the Environmental Protection Agency (EPA) at 40 CFR part 247 that contain the highest percentage of recovered materials practicable, consistent with maintaining a satisfactory level of competition, where the purchase price of the item exceeds \$10,000 or the value of the quantity acquired during the preceding fiscal year exceeded \$10,000; procuring solid waste management services in a manner that maximizes energy and resource recovery; and establishing an affirmative procurement program for procurement of recovered materials identified in the EPA guidelines.

14. PROHIBITION ON CERTAIN TELECOMMUNICATIONS AND VIDEO SURVEILLANCE SERVICES OR EQUIPMENT.

(2 C.F.R. § 200.327 and Appendix II; 2 CFR § 200.216)

Vendor and City agree that both are prohibited from obligating or expending funds under this Contract to:

- (1) Procure or obtain;
- (2) Extend or renew a contract to procure or obtain; or
- (3) Enter into a contract (or extend or renew a contract) to procure or obtain equipment, services, or systems that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system. As described in Public Law 115–232, section 889, covered telecommunications equipment is telecommunications equipment produced by Huawei Technologies Company or ZTE Corporation (or any subsidiary or affiliate of such entities).
 - (i) For the purpose of public safety, security of government facilities, physical security surveillance of critical infrastructure, and other national security purposes, video surveillance and telecommunications equipment produced by Hytera Communications Corporation, Hangzhou Hikvision Digital Technology Company, or Dahua Technology Company (or any subsidiary or affiliate of such entities).
 - (ii) Telecommunications or video surveillance services provided by such entities or using such equipment.
 - (iii) Telecommunications or video surveillance equipment or services produced or provided by an entity that the Secretary of Defense, in consultation with the Director of the National Intelligence or the Director of the Federal Bureau of Investigation, reasonably believes to be an entity owned or controlled by, or otherwise connected to, the government of a covered foreign country.

In implementing the prohibition under Public Law 115–232, section 889, subsection (f), paragraph (1), heads of executive agencies administering loan, grant, or subsidy programs shall prioritize available funding and technical support to assist affected businesses, institutions and organizations as is reasonably necessary for those affected entities to transition from covered communications equipment and services, to procure replacement equipment and services, and to ensure that communications service to users and customers is sustained.

City of Charleston:

Vendor Name:

By: _____

By: _____

Printed Name: _____

Printed Name: _____

Title: _____

Title: _____

Date: _____

Date: _____

EXHIBIT B - FEDERAL WAGE RATES

"General Decision Number: WV20250103 05/30/2025

Superseded General Decision Number: WV20240103

State: West Virginia

Construction Type: Highway

County: Kanawha County in West Virginia.

HIGHWAY CONSTRUCTION PROJECTS

Note: Contracts subject to the Davis-Bacon Act are generally required to pay at least the applicable minimum wage rate required under Executive Order 14026 or Executive Order 13658. Please note that these Executive Orders apply to covered contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but do not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(1).

If the contract is entered into on or after January 30, 2022, or the contract is renewed or extended (e.g., an option is exercised) on or after January 30, 2022:	<ul style="list-style-type: none">◆ Executive Order 14026 generally applies to the contract.◆ The contractor must pay all covered workers at least \$17.75 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in 2025.
If the contract was awarded on or between January 1, 2015 and January 29, 2022, and the contract is not renewed or extended on or after January 30, 2022:	<ul style="list-style-type: none">◆ Executive Order 13658 generally applies to the contract.◆ The contractor must pay all covered workers at least \$13.30 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours performing on that contract in 2025.

The applicable Executive Order minimum wage rate will be adjusted annually. If this contract is covered by one of the Executive Orders and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must still submit a conformance request.

Additional information on contractor requirements and worker protections under the Executive Orders is available at <http://www.dol.gov/whd/govcontracts>.

Modification Number	Publication Date
0	01/03/2025
1	01/31/2025
2	05/30/2025

	Rates	Fringes
TRAFFIC SIGNALIZATION:		
Groundsman.....	\$ 22.12	3%+25.60

ENGI0132-002 12/01/2024		

	Rates	Fringes
OPERATOR: Crane.....	\$ 40.35	20.30

ENGI0132-003 12/01/2024		

	Rates	Fringes
OPERATOR:		
Backhoe/Excavator/Trackhoe.....	\$ 37.59	20.30

ENGI0132-004 12/01/2024		

	Rates	Fringes
OPERATOR: Bobcat/Skid		
Steer/Skid Loader.....	\$ 37.59	20.30

ENGI0132-005 12/01/2024		

	Rates	Fringes
OPERATOR: Broom/Sweeper.....	\$ 37.59	20.30

ENGI0132-030 12/01/2024		

	Rates	Fringes
OPERATOR: Bulldozer.....	\$ 37.59	20.30

ENGI0132-031 12/01/2024		

	Rates	Fringes
OPERATOR: Drill.....	\$ 37.59	20.30

ENGI0132-032 12/01/2024		

	Rates	Fringes
OPERATOR: Forklift.....	\$ 37.59	20.30

ENGI0132-033 12/01/2024		

	Rates	Fringes
OPERATOR: Grader/Blade.....	\$ 37.59	20.30

ENGI0132-035 12/01/2024		

	Rates	Fringes
--	-------	---------

OPERATOR:
Paver/Spreader/Finish
equipment(asphalt, aggregate,

& concrete).....	\$ 37.59	20.30

ENGI0132-036 12/01/2024		
	Rates	Fringes
OPERATOR: Loader		
Up to six (6) cubic yard		
capacity.....	\$ 37.59	20.30

ENGI0132-037 12/01/2024		
	Rates	Fringes
OPERATOR: Mechanic.....		
	\$ 37.59	20.30

ENGI0132-038 12/01/2024		
	Rates	Fringes
OPERATOR: Post Driver		
(Guardrail/Fences).....		
	\$ 37.59	20.30

* LADC0001-002 12/01/2024		
	Rates	Fringes
TRAFFIC CONTROL PERSON.....		
	\$ 27.91	17.40

* LADC0001-004 12/01/2024		
	Rates	Fringes
LABORER: Grade Checker.....		
	\$ 29.00	17.40

* LADC0001-006 12/01/2024		
	Rates	Fringes
LABORER: Laser Screed Operator...		
	\$ 30.03	17.40

* LADC0001-007 12/01/2024		
	Rates	Fringes
LABORER: Asphalt, Includes		
Raker, Shoveler, Spreader and		
Distributor.....	\$ 29.00	17.40

* LADC0001-008 12/01/2024		
	Rates	Fringes
LABORER: Guardrail		
Installation.....		
	\$ 29.00	17.40

* LADC0001-010 12/01/2024		
	Rates	Fringes
LABORER: Pipelayer.....		
	\$ 29.00	17.40

SUWV2022-023 09/11/2024		
	Rates	Fringes

CARPENTER.....	\$ 27.72	19.44
CEMENT MASON/CONCRETE FINISHER...	\$ 28.67	18.85
IRONWORKER.....	\$ 34.87	19.50
LABORER: Common or General.....	\$ 25.95	16.30
LABORER: Mason Tender - Cement/Concrete.....	\$ 26.59	16.30
OPERATOR: Milling Machine.....	\$ 34.18	18.91
OPERATOR: Roller.....	\$ 29.38	18.60
TRUCK DRIVER: Dump Truck.....	\$ 29.04	16.15

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

=====

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at <https://www.dol.gov/agencies/whd/government-contracts>.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than ""SU"", ""UAVG"", ?SA?, or ?SC? denotes that a union rate was prevailing for that classification in the survey. Example:

PLUM0198-005 07/01/2024. PLUM is an identifier of the union whose collectively bargained rate prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. The date, 07/01/2024 in the example, is the effective date of the most current negotiated rate.

Union prevailing wage rates are updated to reflect all changes over time that are reported to WHD in the rates in the collective bargaining agreement (CBA) governing the classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for those classifications, but that 100% of the data reported for the classifications reflected union rates. EXAMPLE:

UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a weighted union average rate. OH indicates the State of Ohio. The next number, 0010 in the example, is an internal number used in producing the wage determination. The date, 01/01/2024 in the example, indicates the date the wage determination was updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to reflect a weighted average of the current rates in the collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The ""SU"" identifier indicates that either a single non-union rate prevailed (as defined in 29 CFR 1.2) for this classification in the survey or that the rate was derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As a weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SUFL2022-007 6/27/2024. SU indicates the rate is a single non-union prevailing rate or a weighted average of survey data for that classification. FL indicates the State of Florida. 2022 is the year of the survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 6/27/2024 in the example, indicates the survey completion date for the classifications and rates under that identifier.

?SU? wage rates typically remain in effect until a new survey is conducted. However, the Wage and Hour Division (WHD) has the discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The ""SA"" identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007 01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the ?SA? identifier took

effect under state law in the state from which the rates were adopted.

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

- a) a survey underlying a wage determination
- b) an existing published wage determination
- c) an initial WHD letter setting forth a position on a wage determination matter
- d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210.

=====

END OF GENERAL DECISION"



City of Charleston, WV

2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

INSTRUCTIONS TO VENDORS SUBMITTING BIDS

1. REVIEW DOCUMENTS THOROUGHLY: The attached documents contain a solicitation for bids. Please read these instructions and all documents attached in their entirety. These instructions provide critical information about requirements that if overlooked could lead to disqualification of a Vendor's bid. All bids must be submitted in accordance with the provisions contained in these instructions and the Solicitation. Failure to do so may result in disqualification of Vendor's bid.

2. MANDATORY TERMS: The Solicitation may contain mandatory provisions identified by the use of the words "must," "will," and "shall." Failure to comply with a mandatory term in the Solicitation will result in bid disqualification.

2A. PREBID MEETING: The item identified below shall apply to this Solicitation.

☐ A pre-bid meeting will not be held prior to bid opening

☒ A MANDATORY PRE-BID meeting will be held at the following place and time:

Address:	City Engineering Office
	114 Dickinson Street
	Charleston, WV 25301
Date:	Wednesday, August 13, 2025
Time:	10:00am

All Vendors submitting a bid must attend the mandatory pre-bid meeting. Failure to attend the mandatory pre-bid meeting shall result in disqualification of the Vendor's bid. No one individual is permitted to represent more than one vendor at the pre-bid meeting. Any individual that does attempt to represent two or more vendors will be required to select one vendor to which the individual's attendance will be attributed. The vendors not selected will be deemed to have not attended the pre-bid meeting unless another individual attended on their behalf. The required attribution of attendance to a single vendor should be addressed during the pre-bid but may occur at any time deemed appropriate by the City of Charleston, WV.



City of Charleston, WV

2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

An attendance sheet provided at the pre-bid meeting shall serve as the official document verifying attendance. Any person attending the pre-bid meeting on behalf of a Vendor must list on the attendance sheet his or her name and the name of the Vendor he or she is representing.

Additionally, the person attending the pre-bid meeting should include the Vendor's E-Mail address, phone number, and Fax number on the attendance sheet. It is the Vendor's responsibility to locate the attendance sheet and provide the required information. Failure to complete the attendance sheet as required may result in disqualification of Vendor's bid.

All Vendors should arrive prior to the starting time for the pre-bid. Vendors who arrive after the starting time but prior to the end of the pre-bid will be permitted to sign in but are charged with knowing all matters discussed at the pre-bid.

Questions submitted at least five business days prior to a scheduled pre-bid will be discussed at the pre-bid meeting if possible. Any discussions or answers to questions at the pre-bid meeting are preliminary in nature and are non-binding. Official and binding answers to questions will be published in a written addendum to the Solicitation prior to bid opening.

3. VENDOR QUESTION DEADLINE: Vendors may submit questions relating to this Solicitation to the City of Charleston's Purchasing Director. Questions must be submitted in writing. All questions must be submitted on or before the date listed below and to the address listed below to be considered. A written response will be published in a Solicitation addendum if a response is possible and appropriate. Non-written discussions, conversations, or questions and answers regarding this Solicitation are preliminary in nature and are nonbinding.

Submitted emails should have the solicitation number and name in the subject line.

QUESTION SUBMISSION DATE:	Wednesday, August 20, 2025
QUESTION SUBMISSION TIME:	10:00am



City of Charleston, WV

2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Submit Questions to:

Billie S. Hancock, Purchasing Director
City of Charleston
501 Virginia Street East, Room 101 Charleston, WV 25301
Email: bids@cityofcharleston.org

4. BID SUBMISSION: Paper bids will be accepted either by hand delivery or mail. Emailed bids will **not** be accepted. Regardless of delivery method, bids must be **received** by the City on or before the date and time of the bid opening. Any bid received by City staff is considered to be in the possession of the City and will not be returned for any reason.

BID OPENING DATE:	Tuesday, September 2, 2025
BID OPENING TIME:	2:00pm

Submit bids to:

Paper Bids Submitted to:	Billie S. Hancock, Purchasing Director City of Charleston 501 Virginia Street East, Room 101 Charleston, WV 25301
---------------------------------	----------------------------------------------------------------------------------------------------------------------------

5. PAPER BID DOCUMENTS: Each paper bid must be submitted in a sealed envelope with the following information:

5.1 Marked on the outside of the Envelope:

- A.** Vendor Name
- B.** Vendor Address
- C.** Solicitation Number and Name
- D.** BID OPENING DATE and BID OPENING TIME



City of Charleston, WV

2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

5.2 Completed Signed forms to Include with Bid:

1. Pricing Page
2. Contact and Signature Form
3. Purchasing Affidavit
4. Protest Acknowledgement Form
5. Addendum Acknowledgement Form
6. Local Vendor Form (if Applicable)
7. Certification of Insurance
8. Any Required Certifications or License (if Applicable)
9. Any and all additional forms listed in the Specifications or Terms and Conditions
10. Bid Bond (if Applicable)
11. Drug Free Affidavit (if Applicable)
12. Subcontractor List (if applicable)

6. ADDENDUM ACKNOWLEDGEMENT: Changes or revisions to this Solicitation will be made by an official addendum issued by the City. Vendor should acknowledge receipt of all addenda issued with this Solicitation by completing an Addendum Acknowledgment Form, a copy of which is included herewith. Failure to acknowledge addenda may result in bid disqualification. The addendum acknowledgement should be submitted with the bid to expedite document processing.

7. BID FORMATTING: Vendor should type or electronically enter the information onto its bid to prevent errors in the evaluation. Failure to type or electronically enter the information may result in bid disqualification.

8. ALTERNATE MODEL OR BRAND: Any model, brand, or specification listed in this Solicitation establishes the acceptable level of quality only and is not intended to reflect a preference for, or in any way favor, a particular brand or vendor. Vendors may bid alternates to a listed model or brand provided that the alternate is at least equal to the model or brand and complies with the required specifications. The equality of any alternate being bid shall be determined by the City at its sole



City of Charleston, WV

2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

discretion. Any Vendor bidding an alternate model or brand should clearly identify the alternate items in its bid and should include manufacturer's specifications, industry literature, and/or any other relevant documentation demonstrating the equality of the alternate items. Failure to provide information for alternate items may be grounds for rejection of a Vendor's bid.

9. EXCEPTIONS AND CLARIFICATIONS: The Solicitation contains the specifications that shall form the basis of a contractual agreement. Vendor shall clearly mark any exceptions, clarifications, or other proposed modifications in its bid. Exceptions to, clarifications of, or modifications of a requirement or term and condition of the Solicitation may result in bid disqualification.

10. LOCAL VENDOR PREFERENCE: A local vendor may qualify for a competitive advantage applied to its bid when certain conditions are met. The vendor has marked on its bid submission that it is requesting to be considered a local vendor for bid evaluation purposes; the vendor provides documentation evidencing that it has the right to conduct business in the State of West Virginia; and the vendor submits an affidavit confirming that it has paid all applicable business taxes to the City or has a non-delinquent payment plan with the City and has had an active and current business and occupation tax account with the City Collector during the entire preceding one-year period. Competitive advantages shall be applied in the following manner:

1. A competitive advantage of 4% shall be applied to the local vendor's bid when, prior to applying the competitive advantage, the lowest responsible bidder submits a bid that is greater than \$25,000 but does not exceed \$125,000.
2. The competitive advantage of \$5,000 shall be applied to the local vendor's bid when, prior to applying the competitive advantage, the lowest responsible bidder submits a bid that is greater than \$125,000.

11. UNIT PRICE: Unit prices shall prevail in cases of a discrepancy in the Vendor's bid.

12. BUSINESS & OCCUPATION TAX: The City of Charleston broadly imposes a Business & Occupation Privilege Tax for the act or privilege of engaging in business activities within the



City of Charleston, WV

2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

City of Charleston. Business & Occupation Tax is measured by the application of rates against gross receipts or gross income of the business. All business activities are classified, and the classifications are significant because the tax liability varies based on the different rates established for the specific types of business activities. Individuals or businesses who do not have a physical location or office located in the City of Charleston are also subject to Business & Occupation Tax if they:

1. Lease tangible personal property to lessees in Charleston
2. Perform construction or installation contracts in Charleston
3. Render services in Charleston.
4. Business & Occupation Tax should be considered when preparing your bid. If you are uncertain as to your business activity or how your business should properly calculate the tax when preparing your bid, please contact us at botax@cityofcharleston.org.

NOTE: No contract or purchase of materials or equipment will be awarded to a company whose Business & Occupation Tax status is delinquent.

13. NON-RESPONSIBLE: The City reserves the right to reject the bid of any vendor as non-responsible in accordance with W. Va. Code of State Rules § 148- 1-5.3, when the City determines that the vendor submitting the bid does not have the capability to fully perform or lacks the integrity and reliability to assure good-faith performance.”

14. ACCEPTANCE/REJECTION: The City may accept or reject any bid as whole, or in part, and may make partial awards if appropriate and necessary based on unit price.

15. YOUR SUBMISSION IS A PUBLIC DOCUMENT: Vendor’s entire response to the Solicitation and the resulting Contract are public documents. As public documents, they will be disclosed to the public following the bid/proposal opening or award of the contract, as required by the competitive bidding laws of West Virginia Code §§5-22-1 et seq., 5G-1- 1 et seq. and the Freedom of Information Act in West Virginia Code §§ 29B-1-1 et seq. DO NOT SUBMIT MATERIAL YOU CONSIDER TO BE CONFIDENTIAL, A TRADE SECRET, OR OTHERWISE NOT SUBJECT TO PUBLIC DISCLOSURE. Submission of any bid, proposal, or other document to the City constitutes your explicit consent to the subsequent public disclosure of the bid, proposal, or document. The City will disclose any document labeled



City of Charleston, WV

2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

“confidential,” “proprietary,” “trade secret,” “private,” or labeled with any other claim against public disclosure of the documents, to include any “trade secrets” as defined by West Virginia Code § 47-22-1 et seq. All submissions are subject to public disclosure without notice.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

GENERAL TERMS AND CONDITIONS

1. CONTRACTUAL AGREEMENT: Issuance of an Award Document signed by the City of Charleston, WV, constitutes acceptance by the City of this Contract made by and between the City of Charleston and the Vendor. Vendor's signature on its bid, or on the Contract if the Contract is not the result of a bid solicitation, signifies Vendor's agreement to be bound by and accept the terms and conditions contained in this Contract. The plans, specifications, and other specified provisions thereto and Vendor's response thereto, including but not limited to specifications, warranty information, any addendums, and all other information provided by Vendor, are incorporated herein and made a part hereof, collectively, as "Attachment A."

In consideration of such payments and for other good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged, Vendor agrees to provide the Materials and perform the Services in accordance with the provisions of this Agreement, Attachment A, and all other exhibits attached hereto and documents incorporated herein by reference.

The parties acknowledge and agree that Attachment A is intended to and shall supplement the terms of this Agreement, but in the event of any inconsistency between the provisions of this Agreement and Attachment A, City shall have the exclusive right to elect which provision shall control. The parties further acknowledge and agree that in the event of any inconsistency between the Request, including attachments thereto, and Vendor's responses, including any attachments thereto, contained in Attachment A, City shall have the exclusive right to elect which provision shall control.

2. DEFINITIONS: As used in this Solicitation/Contract, the following terms shall have the meanings attributed to them below. Additional definitions may be found in the specifications included with this Solicitation/Contract.

2.1. "City" means the City of Charleston, WV, that is identified on the first page of the Solicitation seeking to procure goods or services under this Contract.

2.2. "Bid" or "Proposal" means the vendor's submitted response to this solicitation.

2.3. "Contract" means the binding agreement that is entered into between the City and the Vendor to provide the goods or services requested in the Solicitation.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

2.4. “Solicitation” means the official notice of an opportunity to supply the City with goods or services that is published by the City.

2.5. “Vendor” or “Vendors” means any entity submitting a bid in response to the Solicitation, the entity that has been selected as the lowest responsible bidder, or the entity that has been awarded the Contract, as context requires.

3. CONTRACT TERM; RENEWAL; EXTENSION: The term of this Contract shall be determined in accordance with the category that has been identified as applicable to this Contract below:

☐ Term Contract Initial Contract Term: The Initial Contract Term will be for a period of _____. Renewal Term: This Contract may be renewed upon the mutual written consent of the City and the Vendor. All requests for renewal must be submitted in writing thirty (30) days prior to the expiration date of the initial contract term or an appropriate renewal term. A Contract renewal shall be in accordance with the terms and conditions of the original contract. Unless otherwise specified below, renewal of this Contract is limited to _____ successive one (1) year periods. Automatic renewal of this Contract is prohibited. This Contract becomes effective on the effective start date listed on the Notice to Proceed.

☐ Fixed Period Contract: This Contract becomes effective upon Vendor’s receipt of the notice to proceed and must be completed within _____ days or by/on the date listed in Section _____ of the Solicitation.

☐ Fixed Period Contract with Renewals: This Contract becomes effective upon Vendor’s receipt of the notice to proceed and part of the Contract more fully described in the attached specifications must be completed within _____ days or by/on the date listed in Section _____ of the Solicitation. Upon completion of the work covered by the preceding sentence, the vendor agrees that:

☐ the contract will continue for _____ years;

☐ the contract may be renewed for _____ successive _____ year periods or shorter periods, provided that they do not exceed the total number of months contained in all available renewals. Automatic renewal of this Contract is prohibited. Renewals must be approved by the Vendor and City.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

[] One-Time Purchase: The term of this Contract shall run from the issuance of the Award Document until all of the goods contracted for have been delivered, but in no event will this Contract extend for more than one fiscal year.

[x] Construction/Project: This Contract becomes effective on the effective start date listed on the Notice to Proceed and must be completed within 9 (nine) months of award.

[] Other: _____. effective for one year from the date the delivery order is issued. No delivery order may be extended beyond one year after this Contract has expired. This Contract becomes effective on the effective start date listed on the Notice to Proceed.

4. PROCUREMENT OF AGREEMENT: Vendor represents and warrants that no person or selling agency has been employed or retained to solicit or secure this Agreement upon an agreement or understanding for a commission, percentage, brokerage fee, contingent fee, or any other compensation.

Vendor represents and warrants that it is authorized to do business in the State of West Virginia and may lawfully perform the Services and provide the Materials required by this Agreement without violating any Federal, State, or local law or regulation.

The Vendor represents and warrants that the execution, delivery and performance hereof including the performance of the Services and the sale of the Materials have been authorized and approved by all necessary action on its behalf, constitutes its valid and binding obligation and that the same shall not violate any law or agreement binding on or applicable to Vendor.

5. FAIR PRACTICES: Vendor, and each person signing on behalf of Vendor, represents, warrants, and certifies, under penalty of perjury, that to the best of their knowledge and belief:

The prices in Attachment A have been arrived at independently without collusion, consultation, communication, or agreement, for the purpose of restricting competition, as to any matter relating to such price with any other bidder or with any competitor.

Unless otherwise required by law, the prices stated in this Agreement and Attachment A have not been knowingly disclosed by Vendor prior to the proposal opening, directly or indirectly, to any other bidder or to any competitor.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

No attempt has been made or will be made by Vendor to induce any other person, partnership, or corporation to submit or not to submit a proposal for the purpose of restricting competition.

6. AUTHORITY TO PROCEED: Vendor is authorized to begin performance of this contract upon the date of the Notice to Proceed signed by the City Manager or their designee.

7. QUANTITIES: The quantities required under this Contract shall be determined in accordance with the category that has been identified as applicable to this Contract below.

☐ **Open End Contract:** Quantities listed in this Solicitation/Award Document are approximations only, based on estimates supplied by the City. It is understood and agreed that the Contract shall cover the quantities actually ordered for delivery during the term of the Contract, whether more or less than the quantities shown.

☐ **Service:** The scope of the service to be provided will be more clearly defined in the specifications included herewith.

☐ **Combined Service and Goods:** The scope of the service and deliverable goods to be provided will be more clearly defined in the specifications included herewith.

☐ **One-Time Purchase:** This Contract is for the purchase of a set quantity of goods that are identified in the specifications included herewith. Once those items have been delivered, no additional goods may be procured under this Contract without an appropriate change order approved by the Vendor and City.

☒ **Construction:** This Contract is for construction activity more fully defined in the specifications.

8. EMERGENCY PURCHASES: The City may authorize a purchase of goods or services in the open market that Vendor would otherwise provide under this Contract if those goods or services are for immediate or expedited delivery in an emergency. Emergencies shall include, but are not limited to, delays in transportation or an unanticipated increase in the volume of work. An emergency purchase in the open market, approved by the City shall not constitute a breach of this Contract and shall not entitle the Vendor to any form of compensation or damages. This provision does not excuse the City from fulfilling its obligations under a One-Time Purchase contract.

9. REQUIRED DOCUMENTS: In addition to any requirements under the Section of the General Terms and Conditions entitled Licensing, the apparent successful Vendor shall



**Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard
Mitigation Grant Project**

furnish proof of the following licenses, certifications, and/or permits upon request and in a form acceptable to the City. The request may be prior to or after contract award at the City's sole discretion. All of the items checked in this section must be provided to the City by the Vendor as specified:

☒ **LICENSE(S) : WV CONTRACTOR's LICENSE**

☐ **CERTIFICATION(S)**

☐ **PERMIT(S)**

☐

☐

☐ The apparent successful Vendor shall also furnish proof of any additional licenses or certifications contained in the specifications, regardless of whether or not that requirement is listed above.

10. INSURANCE: The apparent successful Vendor shall furnish proof of the insurance identified by a checkmark below prior to Contract award and shall name the City as an additional insured for purposes of this Agreement and the indemnity provisions herein. Vendor shall be responsible for the payment of all deductibles. All policies shall provide primary coverage, shall reflect that the Vendor is responsible for any and all deductibles, and shall otherwise be in such form and with such endorsements and riders as the City shall specify. Insurance coverage required herein shall be furnished by a company approved by the insurance commission of the State of West Virginia. In the event that Vendor's insurer denies coverage or terminates Vendor's insurance coverage, the City may, at its option, terminate this Agreement immediately. The insurance coverages identified below must be maintained throughout the life of this contract. Thirty (30) days prior to the expiration of the insurance policies, Vendor shall provide the City with proof that the insurance mandated herein has been continued. Vendor must also provide the City with immediate notice of any changes in its insurance policies, including but not limited to, policy cancellation, policy reduction, or change in insurers. The apparent successful Vendor shall also furnish proof of any additional insurance requirements contained in the specifications prior to Contract award, regardless of whether that insurance requirement is listed in this section. Vendor must maintain:



**Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard
Mitigation Grant Project**

☒ Commercial General Liability Insurance in at least an amount of: \$1,000,000.00 per occurrence.

☒ Automobile Liability Insurance in at least an amount of: \$1,000,000.00 per occurrence.

☐ Professional/Malpractice/Errors and Omission Insurance in at least an amount of: _____ per occurrence.

☐ Commercial Crime and Third Party Fidelity Insurance in an amount of: _____ per occurrence.

☐ Cyber Liability Insurance in an amount of: _____ per occurrence.

☐ Builders Risk Insurance in an amount equal to 100% of the amount of the Contract.

☐ Pollution Insurance in an amount of: _____ per occurrence.

☐ Aircraft Liability in an amount of: _____ per occurrence.

11. WORKERS' COMPENSATION INSURANCE: Vendor shall comply with laws relating to workers' compensation, shall maintain workers' compensation insurance when required, and shall furnish proof of workers' compensation insurance upon request.

12. LIQUIDATED DAMAGES: This clause shall in no way be considered exclusive and shall not limit the City's right to pursue any other available remedy. Vendor shall pay liquidated damages in the amount specified below or as described in the specifications:

☐ _____ for _____.

☐ Liquidated Damages Contained in the Specifications.

☒ Liquidated Damages Are Not Included in this Contract.

13. ACCEPTANCE: Vendor's signature on its bid, or on the certification and signature page, constitutes an offer to the City that cannot be unilaterally withdrawn, signifies that the product or service proposed by vendor meets the mandatory requirements contained in the Solicitation for that product or service, unless otherwise indicated, and signifies acceptance of the terms and conditions contained in the Solicitation unless otherwise indicated.

14. PRICING: The pricing set forth herein is firm for the life of the Contract, unless specified elsewhere within this Solicitation/Contract by the City. A Vendor's inclusion of price adjustment provisions in its bid, without an express authorization from the City in the



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Solicitation to do so, may result in bid disqualification. Notwithstanding the foregoing, Vendor must extend any publicly advertised sale price to the City and invoice at the lower of the contract price or the publicly advertised sale price.

15. PAYMENT IN ARREARS: Payments for goods/services will be made in arrears only upon receipt of a proper invoice, detailing the goods/services provided or receipt of the goods/services, whichever is later. Notwithstanding the foregoing, payments for software licenses, subscriptions, or maintenance may be paid monthly or annually in advance.

Requests for payment for Materials provided and Services performed in any month shall be prepared and submitted monthly by Vendor in the form of a proper detailed invoice. The City will pay proper requests for payments within thirty (30) days following City's receipt of a proper request for payment. For contracts involving construction services or architecture and engineering services, the City may withhold ten percent (10%) of each interim payment. Vendor shall provide a certified payroll with each invoice submitted. **Invoices shall be mailed to: City Manager, City of Charleston, P.O. Box 2749, Charleston, WV 25330, or hand delivered to City Manager, 501 Virginia Street East, Charleston, WV.**

City may reject any Services or Materials that do not conform to this Agreement or Attachment A, provided that approval shall not be unreasonably withheld. No payment shall be made until said services are performed to the satisfaction of the City. Vendor shall immediately correct such non-conforming Services or Materials without additional cost to City.

City agrees to pay Vendor the retainage amount accrued and the remaining Total Contract Amount within thirty (30) working days of completion of all the following:

1. Inspection of the Materials and Services by City;
2. Acceptance of the Materials by City;
3. Timely completion of the Services to the satisfaction of City; and
4. Receipt by City of a proper invoice from Vendor.

16. TAXES: The Vendor shall pay and be solely responsible for any applicable sales, use, personal property, or any other taxes directly or indirectly arising out of this Contract and the transactions contemplated thereby, including but not limited to municipal Business and Occupation Taxes. The City is exempt from federal and state taxes and will not pay or reimburse such taxes.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

17. ADDITIONAL FEES, INTEREST: Vendor is not permitted to charge additional fees or assess additional charges that were not either expressly provided for in the solicitation published by the City, included in the Contract, or included in the unit price or lump sum bid amount that Vendor is required by the solicitation to provide. Including such fees or charges as notes to the solicitation may result in rejection of Vendor's bid. Requesting such fees or charges be paid after the contract has been awarded may result in cancellation of the contract.

18. CANCELLATION: City shall have the right to terminate this Agreement, in whole or in part, in accordance with the following, or for reasons set forth elsewhere in this Agreement:

- A. Upon the default by Vendor under any covenant or other term or condition of this Agreement or Attachment A, or if any warranty or representation made by Vendor is untrue in any material respect; or
- B. Upon Vendor's becoming insolvent or upon commencement under the Bankruptcy Act of any similar proceeding either voluntarily or involuntarily; or
- C. If funds are not appropriated by City for the purposes of this Agreement. In the event of City's termination pursuant to this section of the Agreement, City agrees to compensate Vendor for all Services and Materials for which funds were appropriated, and which were satisfactorily performed through the date of termination; or
- D. Upon failure by Vendor to perform the Services with sufficient and qualified employees, sufficient and suitable equipment, or with sufficient and suitable Materials to assure the prompt and satisfactory completion of the work; or
- E. If Vendor performs the Services unsuitably or neglects or refuses to remove and replace non-conforming Materials or to correct non-conforming Services to the satisfaction of the City; or
- F. If Vendor fails to maintain General Liability insurance as required herein, with the City and its agents as additional insureds, with limits of at least \$1 million; or



**Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard
Mitigation Grant Project**

- G. For any other lawful reason, provided that the City provides thirty (30) days' written notice to the Vendor.

Upon such termination resulting from the default of Vendor, City may, in addition to its other rights and remedies hereunder, institute a civil action for damages or specific performance and exercise such other rights and remedies as it may have under applicable law.

In the event of termination, all finished or unfinished documents, data, studies, surveys, drawings, maps, models, photographs, and reports prepared by Vendor pursuant to this Agreement shall, at the option of the City, become property of the City.

19. TIME: Time is of the essence regarding all matters of time and performance in this Contract. Vendor shall complete the Services to City's satisfaction:

☒ Project will be substantially completed within 7 months of Notice to Proceed

☐ Within a reasonable time period of receiving the notice to proceed

unless the term herein shall be extended by the mutual written agreement of the Parties hereto. If Vendor fails to perform its obligation to provide the Materials and complete the Services by such date, or otherwise breaches the terms of this Agreement or Attachment A, City may, but without any obligation to do so, terminate this Agreement immediately, call Vendor's bonds, engage another vendor or vendors to provide the Materials and/or complete the Services as City may determine, and seek monetary damages from Vendor in addition to other remedies available under this Agreement, Attachment A, or applicable law. Vendor shall not be responsible for: (1) delays occasioned by circumstances beyond the control of Vendor, including property access, labor strikes, lockouts and unavoidable casualties or causes; or (2) changes ordered by City, unless the changes were necessary to correct defects or non-compliance of the Services or the Materials.

20. COMPLIANCE WITH LAWS: Vendor shall comply with all applicable federal, state, and local laws, regulations, and ordinances. By submitting a bid, Vendor acknowledges that it has reviewed, understands, and will comply with all applicable laws, regulations, and ordinances. If Vendor fails to comply with the aforementioned laws and/or requirements, the City may, at its discretion, take appropriate action, including, but not limited to, calling Vendor's bonds and/or terminating this Agreement immediately.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

20.1. SUBCONTRACTOR COMPLIANCE: Vendor shall notify all subcontractors providing commodities or services related to this Contract that, as subcontractors, they too are required to comply with all applicable laws, regulations, and ordinances. Notification under this provision must occur prior to the performance of any work under the contract by the subcontractor.

21. PROHIBITED ACTIVITY: During the performance of this Agreement, Vendor or personnel employed hereunder shall not use their position as a Contractor for the City of Charleston to directly promote political activities, inherently religious activities, lobbying, political patronage, or nepotism activities.

22. DILIGENT REVIEW BY VENDOR AND ABILITY TO PERFORM THE SERVICES: Vendor agrees and acknowledges that:

- A. Vendor has examined and carefully studied this Agreement, Attachment A hereto, and other related data identified in the request for bids and the plans, specifications, and other specified provisions thereto;
- B. Vendor has visited the site of the project, has become familiar with it, and is satisfied as to the general, local, and site conditions that may affect cost, progress, provision of the Materials, and performance of the Services;
- C. Vendor has obtained and carefully studied (or assumes responsibility for doing so) all additional or supplementary examinations, investigations, explorations, tests, studies, and data concerning conditions (surface, subsurface, and underground facilities) at or contiguous to the site of the project which may affect cost, progress, provision of the Materials or performance of the Services or which relate to any aspect of the means, methods, techniques, sequences, and procedures of construction expressly required by this Agreement, Attachment A, and all safety precautions and programs incident thereto;
- D. Vendor does not consider that any further examinations, investigations, explorations, tests, studies, or data are necessary for the provision of the Materials or performance of the Services at the Total Contracted Price stated herein.



**Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard
Mitigation Grant Project**

- E. Vendor has given the City Manager and/or the design engineer written notice of all conflicts, errors, ambiguities, or discrepancies that Vendor has discovered in this Agreement and Attachment A hereto, and the written resolution thereof by the City Manager and/or design engineer is acceptable to Vendor; and
- F. This Agreement and Attachment A hereto are generally sufficient to indicate and convey understanding of all terms and conditions for provision of the Materials and performance of the Services to the satisfaction of the City.

23. TRAFFIC CONTROL: Vendor shall always conduct work in such a manner and in such sequence as will assure the least interference with traffic. During the performance of the Services, Vendor shall be solely responsible for putting in place adequate safety measures and warnings for both pedestrians and vehicular traffic, including, but not limited to, barricades, flashing lights, flaggers, and all other measures required by law or necessary under the circumstances. Vendor should anticipate pedestrian traffic and shall provide adequate measures to protect the work and the public.

24. RESPONSIBILITY OF AVOIDING STRUCTURES: Vendor shall assume full responsibility for the protection of all property owned by City or by any third party in the vicinity of the project. Vendor shall notify the City Manager if Vendor's work encroaches on structures or property owned by a third party in the area of the project. Vendor shall replace or repair at Vendor's expense any and all property of any kind damaged as a result of Vendor's work at no additional cost to the City.

25. ACCESS: City agrees to take all actions necessary to allow Vendor and its subcontractor(s) authority to enter the property upon which Vendor's Services are to be performed. Vendor shall take all reasonable precautions to minimize any damage to the property covered by the Agreement and to any adjoining property. Any cost of correction, repair, or replacement to such property, or adjoining properties, shall be borne by Vendor.

26. CLEAN UP: Vendor shall pick up all debris and materials resulting from its work and remove it from the job site. Vendor shall dispose of all debris resulting from its work at its own expense and in conformity with applicable Federal, State, and local health and sanitary codes and laws. Vendor shall be responsible for complete and lawful removal of any and all hazardous material/debris resulting from Vendor's work activities from the job site. The final clean up shall be reviewed and approved by the City Engineer prior to final payment.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

27. DISPUTE RESOLUTION, JURISDICTION AND VENUE: Any references to arbitration contained in the Agreement are hereby deleted, as is any requirement to waive a jury trial. If any breach, default, or other dispute arises out of this Agreement, the Parties agree that they will exercise good faith and commercially reasonable efforts to resolve said breach, default, or other dispute through negotiation and/or mediation. If the parties cannot resolve the matter without litigation, the Parties acknowledge and agree that either the Circuit Court of Kanawha County, West Virginia, or the Federal District Court for the Southern District of West Virginia shall have exclusive jurisdiction to resolve the breach, default, or other dispute giving rise to the litigation. Any language requiring or permitting disputes under the Agreement to be resolved in any other court is deleted. Vendor acknowledges and agrees that resolution agreements reached through consultation and negotiation, or any other form of dispute resolution, may be subject to approval by City's governing body during a public meeting.

28. MODIFICATIONS: This writing is the parties' final expression of intent. Notwithstanding anything contained in this Contract to the contrary no modification of this Contract shall be binding without mutual written consent of the City and the Vendor and, for any modification to be enforced against City, shall reference the Section of this Agreement to be modified and specifically identify the term, condition, or obligation to be modified. Any change to existing contracts that adds work or changes contract cost, and was not included in the original contract, must be approved by the City.

29. WAIVER: The failure of either party to insist upon a strict performance of any of the terms or provision of this Contract, or to exercise any option, right, or remedy herein contained, shall not be construed as a waiver or a relinquishment for the future of such term, provision, option, right, or remedy, but the same shall continue in full force and effect. Any waiver must be expressly stated in writing and signed by the waiving party.

30. SUBSEQUENT FORMS: The terms and conditions contained in this Contract shall supersede any and all subsequent terms and conditions which may appear on any form documents submitted by Vendor to the City, such as price lists, order forms, invoices, sales agreements, or maintenance agreements, and includes internet websites or other electronic documents. Acceptance or use of Vendor's forms does not constitute acceptance of the terms and conditions contained thereon.

31. ASSIGNMENT: Neither this Contract nor any monies due, or to become due hereunder, may be assigned by the Vendor without the express written consent of the City.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

32. WARRANTY: The Vendor expressly warrants that the goods and/or services covered by this Contract will: (a) conform to the specifications, drawings, samples, or other description furnished or specified by the Agency; (b) be merchantable and fit for the purpose intended; and (c) be free from defect in material and workmanship.

33. CITY EMPLOYEES: City employees are not permitted to utilize this Contract for personal use, and the Vendor is prohibited from permitting or facilitating the same.

34. PRIVACY, SECURITY, AND CONFIDENTIALITY: The Vendor agrees that it will not disclose to anyone, directly or indirectly, any such personally identifiable information or other confidential information gained from the City, unless the individual who is the subject of the information consents to the disclosure in writing or the disclosure is made pursuant to the City's policies, procedures, and rules.

35. YOUR SUBMISSION IS A PUBLIC DOCUMENT: Vendor's entire response to the Solicitation and the resulting Contract are public documents. As public documents, they will be disclosed to the public following the bid/proposal opening or award of the contract, as required by the Freedom of Information Act West Virginia Code §§ 29B-1-1 et seq. DO NOT SUBMIT MATERIAL YOU CONSIDER TO BE CONFIDENTIAL, A TRADE SECRET, OR OTHERWISE NOT SUBJECT TO PUBLIC DISCLOSURE. Submission of any bid, proposal, or other document to the City constitutes your explicit consent to the subsequent public disclosure of the bid, proposal, or document. The City will disclose any document labeled "confidential," "proprietary," "trade secret," "private," or labeled with any other claim against public disclosure of the documents, to include any "trade secrets" as defined by West Virginia Code § 47-22-1 et seq. All submissions are subject to public disclosure without notice.

36. LICENSING: In accordance with West Virginia Code of State Rules § 148-1-6.1.e, Vendor must be licensed and in good standing in accordance with any and all state and local laws and requirements by any state or local agency of West Virginia, including, but not limited to, the West Virginia Secretary of State's Office, the West Virginia State Tax Division, West Virginia Offices of the Insurance Commissioner, or any other state agency or political subdivision. Obligations related to political subdivisions may include, but are not limited to, business licensing, business and occupation taxes, inspection compliance, permitting, etc. Upon request, the Vendor must provide all necessary releases to obtain information to enable the City to verify that the Vendor is licensed and in good standing with the above entities.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

36.1 SUBCONTRACTOR COMPLIANCE: Vendor shall notify all subcontractors providing commodities or services related to this Contract that, as subcontractors, they too are required to be licensed, in good standing, and up to date on all state and local obligations as described in this section. Obligations related to political subdivisions may include, but are not limited to, business licensing, business and occupation taxes, inspection compliance, permitting, etc. Notification under this provision must occur prior to the performance of any work under the contract by the subcontractor.

37. ANTITRUST: In submitting a bid to, signing a contract with, or accepting an Award Document from the City, the Vendor agrees to convey, sell, assign, or transfer to the City all rights, title, and interest in and to all causes of action it may now or hereafter acquire under the antitrust laws of the United States and the State of West Virginia for price fixing and/or unreasonable restraints of trade relating to the particular commodities or services purchased or acquired by the City. Such assignment shall be made and become effective at the time the City tenders the initial payment to Vendor.

38. VENDOR NON-CONFLICT: Vendor represents and warrants that neither it nor any of its directors, officers, members, partners or employees, has any interest nor shall they acquire any interest, directly or indirectly, which would or may conflict or compromise in any manner or degree with the performance of the Services or the provision of Materials as herein provided. Any such interests shall be promptly presented in detail to the City.

39. VENDOR RELATIONSHIP: The relationship of the Vendor to the City shall be that of an independent contractor, and no principal-agent relationship or employer-employee relationship is contemplated or created by this Contract. The Vendor, as an independent contractor, is solely liable for the acts and omissions of its employees and agents. Vendor shall be responsible for selecting, supervising, and compensating any and all individuals employed pursuant to the terms of this Solicitation and resulting contract. Neither the Vendor nor any employees or subcontractors of the Vendor shall be deemed to be employees of the City for any purpose whatsoever. Vendor shall be exclusively responsible for payment of employees and contractors for all wages and salaries, taxes, withholding payments, penalties, fees, fringe benefits, professional liability insurance premiums, contributions to insurance and pension, or other deferred compensation plans, including but not limited to, Workers' Compensation and Social Security obligations, licensing fees, etc. and the filing of all necessary documents, forms, and returns pertinent to all of the foregoing. Vendor shall hold harmless the City and shall provide the City with a defense



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

against any and all claims, including, but not limited to, the foregoing payments, withholdings, contributions, taxes, Social Security taxes, and employer income tax returns.

40. INDEMNIFICATION: In addition to, and not in lieu of the indemnity provisions set forth in this Section, Vendor agrees that it shall indemnify, defend and hold harmless City, its officers, employees and agents (hereinafter collectively, "City" for purposes of the indemnity, defense, hold harmless and insurance obligations contained in this Agreement) from and against any and all claims, demands, obligations, causes of action, lawsuits, fines, costs, judgments and damages of any character whatsoever, and all expenses associated therewith (including, but not limited to, reasonable attorney's fees and costs), arising from or related in any way to: (i) the operations of Vendor, its officers, agents, employees, subcontractors and its related or affiliated companies (hereinafter collectively, "Vendor" for purposes of the indemnity, defense and hold harmless obligations contained in this Agreement); (ii) Vendor's provision of the Services or Materials; (iii) any act or omission, negligence or misconduct of Vendor; (iv) a breach of this Agreement; (v) failure of Vendor to complete any required work as specified in the Agreement; or (vi) failure of Vendor to perform any obligation contained in the Agreement or otherwise agreed to by Vendor, whether written or oral. Vendor specifically acknowledges that the indemnification, defense, and hold harmless obligations imposed by this Agreement require Vendor to indemnify and defend City regardless of whether or not any claimant or litigant also alleges that City was negligent. Further, Vendor agrees that its duty to defend and indemnify City does not require a judicial determination of the Vendor's negligence as a precondition of the duty to indemnify and defend City.

In addition to, and not in lieu of the indemnity provisions set forth in this Section, Vendor shall be solely responsible for all physical injuries or death to its officers, agents, employees and subcontractors and, consistent with the obligations imposed by this Agreement, shall indemnify, defend and hold harmless City for such injury or death. Vendor shall be solely responsible for the safety and protection of all of its employees, whether due to the acts and omissions, negligence, fault, or default of Vendor or not. Vendor hereby agrees to purchase and carry workers' compensation insurance for all of its employees and to ensure that all of its subcontractors purchase and carry workers' compensation insurance for all of their employees.

In addition to, and not in lieu of the indemnity provisions set forth in this Section, Vendor shall be solely responsible for any and all damage to any property of the City or of any third-



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

party related in any way to Vendor's operations, provision of the Services or Materials, or any act or omission, negligence or misconduct of Vendor. Consistent with the obligations imposed by this Agreement, Vendor shall indemnify, defend and hold harmless City for any and all such damage, and, in the event of damage to any property of City, shall promptly reimburse City for all costs and expenses of any character upon Vendor's receipt of a demand for reimbursement by City.

The indemnity provided for in the Section herein shall be deemed in addition to and in no way a limitation upon the right of common law indemnification of City, its officers, employees, and agents from Vendor.

41. NO DEBT CERTIFICATION: The City is prohibited from awarding a contract to any bidder that owes a debt to the City. By submitting a bid, or entering into a contract with the City, Vendor is affirming that (1) for construction contracts, the Vendor is not in default on any monetary obligation owed to the City (2) for all other contracts, neither the Vendor nor any related party owe a debt as defined above, and neither the Vendor nor any related party are in employer default as defined in the statute cited above unless the debt or employer default is permitted under the statute.

42. REPORTS: Vendor shall provide the City with the following reports identified by a checked box below:

☒ [x] Such reports as the City may request.

☐ [] Quarterly reports detailing the total quantity of purchases in units and dollars, along with a listing of purchases by agency.

43. BOOKS, RECORDS, AND AUDIT BY CITY: All vouchers or invoices presented for payment to be made hereunder, and the books, records, and accounts upon which said vouchers or invoices are based, are subject to audit by appropriate City officials. Vendor agrees to maintain and retain separate and accurate books, records, documents, and other evidence and accounting procedures and practices that sufficiently and properly reflect all direct and indirect costs of any nature expended in the performance of this Agreement.

Vendor agrees to retain all books, records, and other documents relevant to this Agreement for ten years after the final payment or termination of this Agreement, whichever is later. City, State, and Federal auditors, and any other persons duly authorized by the City, shall have full access to and the right to examine any of said materials during said period.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Vendor shall submit any and all documentation and justification in support of expenditures or fees under this Agreement as may be required by City.

Vendor shall not be entitled to final payment under the Agreement until all requirements of this Agreement and Attachment A have been satisfactorily met.

44. VENDOR'S REPRESENTATION, WARRANTIES, AND GUARANTEE; PROHIBITION AGAINST USED OR REFURBISHED: Unless otherwise agreed to in writing by City or expressly permitted by City in Attachment A, Vendor hereby represents, warrants and agrees that the Materials used in connection with the Agreement are new, in good and marketable condition, have never been used, are sufficient for their intended purposes, are in compliance with the specifications in Attachment A, and that Vendor owns them and has the right to sell and convey them to City free of liens and encumbrances. Vendor hereby assigns to City all rights to any and all warranties and/or guarantees, whether express or implied, made to Vendor by the manufacturers or distributors of the Materials or any part thereof. Vendor agrees to assist the City in enforcing any and all warranties and/or guarantees related to the Materials.

Vendor further warrants that, if any of its completed Services fail to conform to this Agreement or Attachment A, Vendor shall, at its own expense, and provided Vendor is notified of such defect or non-conformity within one year of the completion of the Services, either perform corrective services at no cost to City as may be required to correct such defect or non-conformity or refund to City the amount paid to Vendor for Services that are defective or non-conforming.

45. PROTECTION OF WORK AND MATERIALS; SUSPENSION OF WORK: Vendor shall at all times be solely responsible for the protection of all work and Materials against damage or injury. In the event of temporary suspension of work for any reason, including, but not limited to, inclement weather, Vendor shall immediately take all action(s) necessary to ensure the protection of all work and Materials against damage or injury.

City may suspend work if the City Manager or his designee determines that suspension is in the City's best interest and/or the City elects to terminate this Agreement for any of the provisions contained in this Agreement. The City Manager and/or the designee will deliver to Vendor a Notice of Suspension specifying the extent and duration of the suspension and the effective date thereof. Upon receipt of such Notice of Suspension, Vendor shall immediately proceed to stop work, as specified in the notice, place no further subcontracts or orders for materials (except as necessary to complete any work that is not subject to suspension), and



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

take all action(s) necessary, including any action(s) that the City Manager may direct, for the protection and preservation of the Materials and any property related to this Agreement.

If, in the opinion of the City Manager, any work or Materials have been damaged or injured by reason of failure on the part of the Vendor or his subcontractors to protect their work or Materials, such Materials shall be removed and replaced at the expense of the Vendor.

46. GOVERNING LAW: The Agreement shall be deemed to be executed in the City of Charleston, State of West Virginia, regardless of the domicile of Vendor, and shall be governed by the laws of the City of Charleston and State of West Virginia. This provision replaces any references to any other State's governing law.

The parties agree that any and all claims asserted by or against City arising under this Agreement, or related thereto, shall be heard and determined either in the United States District Court for the Southern District of West Virginia or in the Circuit Court of Kanawha County, West Virginia.

47. CONDITIONS PRECEDENT: This Agreement shall neither be binding on City nor effective until the execution of this Agreement by the City Manager or their authorized representative. The requirements of this section of this Agreement shall be in addition to, and not in lieu of, any approval or authorization otherwise required for this Agreement to be effective and for the expenditure of City funds.

48. GENERAL RELEASE; WAIVER OF MECHANIC'S LIENS: The acceptance by the Vendor and its assignees of the final payment under this Agreement, whether by check, voucher, judgment of any court of competent jurisdiction or any other administrative means, shall constitute and operate as a general release to City from any and all claims of and liability to Vendor arising out of the performance of this Agreement. Vendor waives its right to file a mechanic's or other lien in connection with the provision of the Services or Materials.

49. NO CLAIM AGAINST OFFICER, AGENT, OR EMPLOYEES: No claim whatsoever shall be made by Vendor against any officer, employee, or agent of City for, or on account of, anything done or omitted in connection with this Contract.

50. NOTICE BETWEEN VENDOR AND CITY: Vendor and City hereby designate the business mailing addresses set forth in this Agreement as the places where all notice, directions, or communications from one such party to the other party shall be delivered, or to which they shall be mailed. Such address may be changed at any time by either party by written notice to the other party in the manner prescribed herein.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Vendor shall identify and provide a superintendent, foreman, or supervisor who shall have the authority to act for Vendor for the purposes of this Agreement.

51. FORCE MAJEURE: In the event of any condition or event, not existing as of the date of execution of the Agreement, not reasonably foreseeable as of such date, and not reasonably within the control of the parties which prevents in whole or in material part the performance of either party of its obligations hereunder, the obligations of each party to perform under the Agreement shall be suspended until the cause no longer prevents or makes impracticable either party's performance at which time all obligations shall resume. Either party shall have the right to terminate this Agreement upon written notice to the other should the condition or event continue for a period of two (2) days or more. Force Majeure events or conditions shall include, but not be limited to, riots, war, governmental action, strikes or lockouts (other than the parties), epidemics, floods, earthquakes, and explosions.

52. ENTIRE AGREEMENT: This Agreement, including Attachment A and all other exhibits attached hereto, and documents incorporated herein by reference, constitutes the entire Agreement between City and Vendor and supersedes all prior or contemporaneous communications, whether electronic, oral, or written, between City and Vendor.

53. HEADINGS: The section headings and subheadings contained in this Agreement are included for convenience only and shall not limit or otherwise affect the terms of this Agreement.

54. SEVERABILITY: If any provision of this Agreement is held invalid, the remainder of the Agreement shall not be affected thereby, and all other parts of this Agreement shall nevertheless be in full force or effect.

55. SURVIVAL: The insurance and indemnity obligations contained in this Agreement herein shall remain in full force and effect and shall survive the completion or earlier termination of this Agreement.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

ADDITIONAL TERMS AND CONDITIONS (Construction Contracts Only)

1. CONTRACTOR'S LICENSE: As of June 15, 2021, West Virginia Code § 21-11-2 and § 30-42-2 require that all persons desiring to perform contracting work in this state be licensed. The West Virginia Contractors Licensing Board is empowered to issue the contractor's license. Applications for a contractor's license may be made by contacting the West Virginia Contractor Licensing Board. The apparent successful Vendor must furnish a copy of its contractor's license prior to the issuance of a contract award document.

2. BONDS: The following bonds must be submitted:

☒ **BID BOND:** Pursuant to the requirements contained in W. Va. Code § 5-22-1(c), All Vendors submitting a bid on a construction project shall furnish a valid bid bond in the amount of five percent (5%) of the total amount of the bid protecting the State of West Virginia. **THE BID BOND MUST BE SUBMITTED WITH THE BID OR VENDOR'S BID WILL BE DISQUALIFIED.**

☒ **PERFORMANCE BOND:** The apparent successful Vendor shall provide a performance bond in the amount of 100% of the contract. The performance bond must be received by the City prior to Contract award.

☒ **LABOR/MATERIAL PAYMENT BOND:** The apparent successful Vendor shall provide a labor/material payment bond in the amount of 100% of the Contract value. The labor/material payment bond must be delivered to the City prior to Contract award.

☐ **MAINTENANCE BOND:** The apparent successful Vendor shall provide a two (2) year maintenance bond covering the roofing system if the work impacts an existing roof. The amount of the bond must be equal to the price associated with the percentage of the project impacting the roof. The maintenance bond must be issued and delivered to the City prior to Contract award.

At a minimum, all construction projects require a bid bond, performance bond, and labor/material payment bond. Failure on the part of the City to checkmark the required bonds above does not relieve the Vendor from the legal requirement of providing these bonds. In lieu of the Bid Bond, the Vendor may provide certified checks or cashier's checks. Any certified check or cashier's check in lieu of the bid bond must be of the same amount required of the Bid Bond and delivered with the bid.



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

3. DRUG-FREE WORKPLACE AFFIDAVIT: W. Va. Code § 21-1D-5 provides that any solicitation for a public improvement contract requires each Vendor that submits a bid for the work to submit an affidavit that the Vendor has a written plan for a drug-free workplace policy. If the affidavit is not submitted with the bid submission, the City shall promptly request by telephone and electronic mail that the low bidder and second low bidder provide the affidavit within one business day of the request. Failure to submit the affidavit within one business day of receiving the request shall result in disqualification of the bid. To comply with this law, Vendor should complete the enclosed drug-free workplace affidavit and submit the same with its bid. Failure to submit the signed and notarized drugfree workplace affidavit or a similar affidavit that fully complies with the requirements of the applicable code, within one business day of being requested to do so, shall result in disqualification of Vendor's bid. Pursuant to W. Va. Code 21-1D-2(b) and (k), this provision does not apply to public improvement contracts the value of which is \$100,000 or less or temporary or emergency repairs.

3.1. DRUG-FREE WORKPLACE POLICY: Pursuant to W. Va. Code § 21-1D-4, Vendor and its subcontractors must implement and maintain a written drug-free workplace policy that complies with said article. The awarding public authority shall cancel this contract if: (1) Vendor fails to implement and maintain a written drug-free workplace policy described in the preceding paragraph, (2) Vendor fails to provide information regarding implementation of its drug-free workplace policy at the request of the public authority; or (3) Vendor provides to the public authority false information regarding the contractor's drug-free workplace policy. Pursuant to W. Va. Code 21-1D-2(b) and (k), this provision does not apply to public improvement contracts the value of which is \$100,000 or less or temporary or emergency repairs.

4. DRUG FREE WORKPLACE REPORT: Pursuant to W. Va. Code § 21-1D-7b, no less than once per year, or upon completion of the project, every contractor shall provide a certified report to the public authority which let the contract.

4.1. The report shall include:

- (1) Information to show that the education and training service to meet the requirements of West Virginia Code § 21-1D-5 was provided
- (2) The name of the laboratory certified by the United States Department of Health and Human Services or its successor that performs the drug tests



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

(3) The average number of employees in connection with the construction on the public improvement

(4) Drug test results for the following categories, including the number of positive tests and the number of negative tests

(A) Pre-employment and new hires

(B) Reasonable suspicion

(C) Post-accident

(D) Random.

Vendor should utilize the attached Certified Drug Free Workplace Report Coversheet when submitting the report required hereunder. Pursuant to W. Va. Code 21-1D-2(b) and (k), this provision does not apply to public improvement contracts the value of which is \$100,000 or less or temporary or emergency repairs.

5. AIA DOCUMENTS: All construction contracts that will be completed under W. Va. Code § 5-22-1 in conjunction with architectural services procured under W. Va. Code § 5G-1 will be governed by the terms and conditions contained herein, in addition to AIA documents that may be necessary on a case-by-case basis. In any case, the terms and conditions of this document shall prevail over anything contained in the AIA Documents or the Supplementary Conditions.

6. PROHIBITION AGAINST GENERAL CONDITIONS: Notwithstanding anything contained in the AIA Documents or the Supplementary Conditions, the City will not pay for general conditions, winter conditions, or any other condition representing a delay in the contracts. The Vendor is expected to mitigate delay costs to the greatest extent possible, and any costs associated with Delays must be specifically and concretely identified. The City will not consider an average daily rate multiplied by the number of days extended to be an acceptable charge.

7. SUBCONTRACTOR LIST SUBMISSION: In accordance with W. Va. Code § 5-22-1, the apparent low bidder on a contract valued at more than \$250,000.00 for the construction, alteration, decoration, painting, or improvement of a new or existing building or structure shall submit a list of all subcontractors who will perform more than \$25,000.00 of work on the project including labor and materials. (This section does not apply to any other construction projects, such as highway, mine reclamation, water, or sewer projects.) The



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

subcontractor list shall be provided to the City within one business day of the opening of bids for review. If the apparent low bidder fails to submit the subcontractor list, the City shall promptly request by telephone and electronic mail that the low bidder and second low bidder provide the subcontractor list within one business day of the request. Failure to submit the subcontractor list within one business day of receiving the request shall result in disqualification of the bid. If no subcontractors who will perform more than \$25,000.00 of work are to be used to complete the project, the apparent low bidder must make this clear on the subcontractor list, in the bid itself, or in response to the City's request for the subcontractor list.

7.1. Required Information. The subcontractor list must contain the following information:

1. Bidder's name
2. Name of each subcontractor performing more than \$25,000 of work on the project.
3. The license number of each subcontractor, as required by W. Va. Code § 30-42-1 et. seq.
4. If applicable, a notation that no subcontractor will be used to perform more than \$25,000.00 of work. (This item is not required if the vendor makes this clear in the bid itself or in documentation following the request for the subcontractor list.)

7.2. Subcontractor List Submission Form: The subcontractor list may be submitted in any form, as long as the required information noted above is included. If any information is missing from the bidder's subcontractor list submission, it may be obtained from other documents such as bids, emails, letters, etc. that accompany the subcontractor list submission.

7.3. Substitution of Subcontractor: Written approval must be obtained from the City before any subcontractor substitution is permitted.

7.3.1. Substitutions are not permitted unless:

1. The subcontractor listed in the original bid has filed for bankruptcy;



Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

2. The subcontractor in the original bid has been debarred or suspended
3. The contractor certifies in writing that the subcontractor listed in the original bid fails, is unable, or refuses to perform their subcontract.



**Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard
Mitigation Grant Project**

ADDITIONAL TERMS AND CONDITIONS

(Architectural and Engineering Contracts Only)

1. PLAN AND DRAWING DISTRIBUTION: All plans and drawings must be completed and available for distribution at least five business days prior to a scheduled pre-bid meeting for the construction or other work related to the plans and drawings.

2. PROJECT ADDENDA REQUIREMENTS: The Architect/Engineer and/or City shall be required to abide by the following schedule in issuing construction project addenda. The Architect/Engineer shall prepare any addendum materials for which it is responsible, and a list of all vendors that have obtained drawings and specifications for the project. The Architect/Engineer shall then send a copy of the addendum materials and the list of vendors to the City for which the contract is issued to allow the City to make any necessary modifications. The City shall send the addendum to all interested vendors and, if necessary, extend the bid opening date. Any addendum should be received by the City at least fourteen (14) days prior to the bid opening date.

3. PRE-BID MEETING RESPONSIBILITIES: The Architect/Engineer shall be available to attend any pre-bid meeting for the construction or other work resulting from the plans, drawings, or specifications prepared by the Architect/Engineer.

4. AIA DOCUMENTS: All construction contracts that will be completed under W. Va. Code §5-22-1 in conjunction with architectural services procured under W. Va. Code §5G-1 will be governed by the terms and conditions contained herein, in addition to AIA documents that may be necessary on a case-by-case basis. In any case, the terms and conditions of this document shall prevail over anything contained in the AIA Documents or the Supplementary Conditions.

5. GREEN BUILDINGS MINIMUM ENERGY STANDARDS: In accordance with West Virginia Code § 22-29-4, all new building construction projects of public agencies that have not entered the schematic design phase prior to July 1, 2012, or any building construction project receiving state grant funds and appropriations, including public schools, that have not entered the schematic design phase prior to July 1, 2012, shall be designed and constructed complying with the ICC International Energy Conservation Code, adopted by the State Fire Commission, and the ANSI/ASHRAE/IESNA Standard 90.1-2007: Provided, That if any construction project has a commitment of federal funds to pay for a portion of



**Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard
Mitigation Grant Project**

such project, this provision shall only apply to the extent such standards are consistent with the federal standards.



**Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard
Mitigation Grant Project**

Contact and Signature

DESIGNATED CONTACT: Vendor appoints the individual identified in this Section as the Contract Administrator and the initial point of contact for matters relating to this Contract.

(Printed Name and Title) _____

(Address) _____

(Phone Number) _____

(Email address) _____

CERTIFICATION AND SIGNATURE: By signing below, I certify that: I have reviewed this Solicitation/Agreement, including all of these Terms and Conditions as well as Attachment A, in its entirety; that I understand the requirements, terms and conditions, and other information contained herein; that this bid constitutes an offer to the City that cannot be withdrawn; that the product or service proposed meets the mandatory requirements contained in the Solicitation, unless otherwise stated herein; that the Vendor accepts the terms and conditions contained in the Solicitation, unless otherwise stated herein; that I am submitting this bid, offer or proposal for review and consideration; that this bid or offer was made without prior understanding, agreement, or connection with any entity submitting a bid or offer for the same material, supplies, equipment or services; that this bid or offer is in all respects fair and without collusion or fraud; that this Contract is accepted or entered into without any prior understanding, agreement, or connection to any other entity that could be considered a violation of law; that I am authorized by the Vendor to execute and submit this bid, offer, or proposal, or any documents related thereto on Vendor's behalf; that I am authorized to bind the vendor in a contractual relationship; and that to the best of my knowledge, the vendor has properly registered with any entity that may require registration.

VENDOR SIGNATURE

(Company) _____

(Signature) _____

(Printed Name) _____

(Title) _____

(Date) _____



**Solicitation: 2025-41 Chesterfield Avenue Storm Sewer Hazard
Mitigation Grant Project**

(Phone Number) _____

(Email Address) _____

(Mail Address) _____

CITY SIGNATURE

CITY OF CHARLESTON, A WEST VIRGINIA MUNICIPAL CORPORATION

(Signature) _____

(Printed Name) _____

(Title) _____

(Date) _____

(Phone Number) _____

(Email Address) _____

(Mail Address) _____



CITY OF CHARLESTON
DRUG FREE WORKPLACE CONFORMANCE AFFIDAVIT
West Virginia Code §21-1D-5

I, _____, after being first duly sworn, depose and state as follows:

1. I am an employee of _____; and,
 (Company Name)
2. I do hereby attest that _____
 (Company Name)

maintains a written plan for a drug-free workplace policy and that such plan and policy are in compliance with **West Virginia Code §21-1D**.

The above statements are sworn to under the penalty of perjury.

Printed Name: _____

Signature: _____

Title: _____

Company Name: _____

Date: _____

STATE OF WEST VIRGINIA,

COUNTY OF _____, TO-WIT:

Taken, subscribed and sworn to before me this _____ day of _____, _____.

By Commission expires _____

(Seal)

 (Notary Public)

Subcontractor List Submission (Construction Contracts Only)

Bidder's Name: _____

☐ Check this box if no subcontractors will perform more than \$25,000.00 of work to complete the project.

Subcontractor Name	License Number if Required by W. Va. Code § 21-11-1 et. seq.

Attach additional pages if necessary

VENDOR PROTEST ACKNOWLEDGMENT

In the event that any vendor desires to protest City's selection, such vendor (hereinafter "Protestor") shall submit its protest in writing, which must be received by City within seven (7) calendar days of after City Council approves of the award. Provided that the City Manager reserves the right to extend the time for submission of the protest if he determines it is reasonable under the circumstances.

The written protest must be submitted to: **Benjamin Mishoe, City Manager, City of Charleston, 501 Virginia Street, Charleston, WV 25301.**

Only vendors who have submitted a timely and responsive proposal may protest City's selection. No protest may be filed if the RFP is withdrawn or if all proposals received in response to the RFP are rejected.

Protests shall include the following information:

1. The Protestor's name, address, telephone number, and fax number;
2. The solicitation number;
3. A detailed statement of the legal and/ or factual grounds for the protest;
4. Copies of all relevant and supporting documentation, if necessary; and
5. A statement as to the form of resolution or relief sought.

FAILURE TO SUBMIT THIS INFORMATION SHALL BE GROUNDS FOR REJECTION OF THE PROTEST.

The City Manager may refuse to review any protests when the matter involved is the subject of litigation before a court of competent jurisdiction; if the merits have previously been decided by a court of competent jurisdiction; or if it has been decided by the City Manager in a previous protest.

At the time of submitting the written protest, Protestor shall submit a certified check in the amount of one thousand dollars (\$1,000.00) or bond equal to five percent (5%) of the price of the selected proposal, whichever is greater. In the event the proposal being protested is for contracted services, an estimated average of the contract value will be determined in order to calculate the five percent (5%) bond value. This bonding requirement is designed to protect against frivolous claims and unnecessary expenditures of public funds and to allow City to offset any and all costs, fees, expenses or damages of any kind whatsoever incurred by City as the result of an unsuccessful protest.

In the event the protest is unsuccessful, the certified check or bond will be used by City to recoup any and all costs, fees, expenses, or damages of any kind whatsoever incurred by City and related in any way to the unsuccessful protest. Costs, fees, expenses, and damages shall include, but shall not be limited to, increased costs of labor, materials or services resulting from any delay,

professional fees, including, but not limited to, attorney fees, and all costs, fees or expenses of any kind whatsoever related in any way to the unsuccessful protest. By signing this document, Protestor waives the right to receive any money retained by City as set forth herein. If there are any funds remaining after City has recouped amounts as permitted herein, the remaining funds will be returned to Protestor. In the event Protestor is successful, the full amount of the certified check or bond will be returned to Protestor.

Upon receipt of a timely written protest, City shall provide notice of the protest to vendor selected as the successful bidder (hereinafter "Selected Vendor") and provide Selected Vendor with a copy of the written protest and any documents related thereto. **Selected Vendor will have two (2) business days to file a written response to the protest.** A hearing may be held within five (5) business days of the **date of receipt of the written response to the protest by Selected Vendor**; provided that, City may, in its sole discretion, set the date of the hearing beyond the five (5) day time period specified herein if deemed necessary or convenient to do so by City. If a hearing is held, both Protestor and Selected Vendor will have an opportunity to appear and present evidence and testimony in support of their positions. The hearing will be held before the City Manager or his designee. The department head of the department seeking the RFP and the City Attorney shall be in attendance.

A decision will be made by City within five (5) business days of the hearing. Upon a decision having been made, both Protestor and Selected Vendor will be notified in writing of City's decision.

In the event City's selection is reversed, City will reevaluate all proposals which were originally and timely submitted, in accordance with state and city laws and regulations. During the reevaluation, issues addressed during the protest proceedings may be considered.

Once a written protest is filed, no work will be performed by Selected Vendor until such time as City has rendered a final decision on the protest; provided that, if City, in its sole discretion, determines time is of the essence regarding receipt of the goods or completion of the services to be performed, City may permit Selected Vendor to proceed pursuant to its proposal and any Agreement with City, until/unless the protest is successful.

By submitting a proposal, each vendor agrees that the procedure outlined herein is the exclusive remedy available to challenge/protest the award of a contract to a successful bidder. The decision of the city manager is final and is not appealable. Each vendor further agrees that, in the event any qualified vendor fails to submit a written protest and certified check or bond within the time period specified, that vendor thereby forever waives its right to any further claim, action, or remedy, including, but not limited to, the right to bring an action before any administrative agency or any court of competent jurisdiction.

Vendor Signature: _____

Date: _____

Solicitation: 2025-41 Chesterfield Ave. Storm Sewer Hazard Mitigation



ADDENDUM ACKNOWLEDGEMENT FORM

SOLICITATION NO.: 2025-41 Chesterfield Avenue Storm Sewer Hazard Mitigation Grant Project

Instructions: Please acknowledge receipt of all addenda issued with this solicitation by completing this addendum acknowledgment form. Check the box next to each addendum received and sign below. Failure to acknowledge addenda may result in bid disqualification.

Acknowledgment: I hereby acknowledge receipt of the following addenda and have made the necessary revisions to my proposal, plans and/or specification, etc.

Addendum Numbers Received: (Check the box next to each addendum received)

- | | |
|-----------------------------------------|------------------------------------------|
| <input type="checkbox"/> Addendum No. 1 | <input type="checkbox"/> Addendum No. 6 |
| <input type="checkbox"/> Addendum No. 2 | <input type="checkbox"/> Addendum No. 7 |
| <input type="checkbox"/> Addendum No. 3 | <input type="checkbox"/> Addendum No. 8 |
| <input type="checkbox"/> Addendum No. 4 | <input type="checkbox"/> Addendum No. 9 |
| <input type="checkbox"/> Addendum No. 5 | <input type="checkbox"/> Addendum No. 10 |

I understand that failure to confirm the receipt of addenda may be cause for rejection of this bid. I further understand that any verbal representation made or assumed to be made during any oral discussion held between Vendor's representatives and any state personnel is not binding. Only the information issued in writing and added to the specifications by an official addendum is binding.

Company Name:	
Authorized Signature:	
Printed Name:	
Date:	

NOTE: This addendum acknowledgement should be submitted with the bid to expedite document processing



CITY OF CHARLESTON, WEST VIRGINIA

LOCAL VENDOR AFFIDAVIT

Pursuant to § 2-480 of the Charleston City Code, a Local Vendor may qualify for a competitive advantage applied to its bid when certain conditions are met. One condition requires the vendor to submit this affidavit confirming that **(1)** the vendor has paid all applicable business taxes to the City or has a non-delinquent payment plan with the City, and **(2)** the vendor must state that it has had an active and current business & occupation tax account with the City Collector during the entire one-year period prior to the bid opening.

AFFIRMATION: By signing this form, the vendor's authorized signer affirms and acknowledges under the penalty of law for false swearing (W. Va. Code § 61-5-3) that **(1)** the vendor has paid all applicable business taxes to the City or has a non-delinquent payment plan with the City, and **(2)** the vendor has had an active and current business & occupation tax account with the City Collector during the entire one-year period prior to the scheduled bid opening for the procurement listed below.

WITNESS THE FOLLOWING SIGNATURE:

Vendor's Corporate Name: _____

Authorized Signature: _____ Date: _____

(Printed Name and Title)

State of _____

County of _____, to wit:

Taken, subscribed, and sworn before me this _____ day of _____, 20 ____.

[SEAL]

Notary Public

My Commission expires _____, 20 ____.

Name of Procurement: **2025-41 Chesterfield Storm Sewer Project** Bid Opening Date: _____

2025-41 Chesterfield Avenue Storm Sewer Hazard mitigation Grant Project

CITY OF CHARLESTON PURCHASING AFFIDAVIT

VENDOR OWING A DEBT TO THE STATE OR POLITICAL SUBDIVISION:

West Virginia Code § 5A-3-10a provides that: No contract or renewal of any contract may be awarded by the state or any of its political subdivisions to any vendor or prospective vendor when the vendor or prospective vendor or a related party to the vendor or prospective vendor is a debtor and the debt owed is an amount greater than one thousand dollars (\$1,000) in the aggregate.

PUBLIC IMPROVEMENT CONTRACTS & DRUG-FREE WORKPLACE ACT:

If this is a solicitation for a public improvement construction contract, the vendor, by its signature below, affirms that it has a written plan for a drug-free workplace policy in compliance with Article 1D, Chapter 21 of the **West Virginia Code**. The vendor **must** make said affirmation with its bid submission. Further, public improvement construction contracts may not be awarded to a vendor who does not have a written plan for a drug-free workplace policy in compliance with Article 1D, Chapter 21 of the **West Virginia Code** and who has not submitted that plan to the appropriate contracting authority in a timely fashion. For a vendor who is a subcontractor, compliance with Section 5, Article 1D, Chapter 21 of the **West Virginia Code** may take place before their work on the public improvement is begun.

ANTITRUST:

In submitting a bid to any agency for the State of West Virginia, the bidder offers and agrees that if the bid is accepted, the bidder will convey, sell, assign or transfer to the state of West Virginia all rights, title and interest in and to all causes of action it may now or hereafter acquire under the antitrust laws of the United States and the State of West Virginia for a price fixing and/or unreasonable restraints of trade relating to the particular commodities or services purchased or acquired by the state of West Virginia. Such assignment shall be made and become effective at the time the purchasing agency tenders the initial payment to the bidder.

I certify that this bid is made without prior understanding, agreement or connection with any corporation, firm, limited liability company, partnership or person or entity submitting a bid for the same materials, supplies, equipment or services and is in all respects fair and without collusion or fraud. I further certify that I am authorized to sign the certification on behalf of the bidder or this bid.

LICENSING:

Vendors must be licensed and in good standing in accordance with any and all state and local laws and requirements by any state or local agency of West Virginia, including, but not limited to, the West Virginia Secretary of State's Office, the West Virginia Tax Department, the West Virginia Insurance Commission or any other state agencies or political subdivision. Furthermore, the vendor must provide all necessary releases to obtain information to enable the Director or spending unit to verify that the vendor is licensed and in good standing with the above entities.

CONFIDENTIALITY:

The vendor agrees that he or she will not disclose to anyone, directly or indirectly, any such personally identifiable information or other confidential information gained from the agency, unless the individual who is the subject of the information consents to the disclosure in writing or the disclosure is made pursuant to the agency's policies, procedures and rules. Vendor further agrees to comply with the Confidentiality Policies and Information Security Accountability Requirements, set forth in <http://www.state.wv.us/admin/purchase/privacy/noticeConfidentiality.pdf>.

Under penalty of law for false swearing (**West Virginia Code § 61-5-3**), it is hereby certified that the vendor affirms and acknowledges the information in this affidavit and is in compliance with the requirements as stated.

Vendor's Name: _____

Authorized Signature: _____ Date: _____



B&O Tax Overview For Construction Projects

Office of the City Collector

915 Quarrier Street, Suite 4

Charleston, WV 25301

Phone (304) 348-8024 / Fax (304) 347-1810

Website: www.charlestonwv.gov

Email: constructionprojects@cityofcharleston.org



Office of the City Collector

915 Quarrier St., Suite 4 | Charleston, WV 25301 | (304) 348-8024 | (304) 348-0734 (fax)

www.charlestonwv.gov

constructionprojects@cityofcharleston.org

Construction Projects Handbook Table of Contents

<u>Topic</u>	<u>Page(s)</u>
Introduction to Charleston Municipal Business and Occupation Tax.....	3
Business & Occupation Tax Overview.....	4
Business & Occupation Tax Contracting Frequently Asked Questions.....	5-6
State of West Virginia Code for Construction Projects.....	7-8
Code of the City of Charleston – Business & Occupation Privilege Tax.....	9-14
Procedures for Authorization to Release Final Payment/Retainage.....	15

Appendix:

- (A) Business Registration Application
- (B) Business & Occupation Tax Return and Instructions
- (C) City Service Fee Return and Instructions
- (D) Subcontractor/Supplier/Installation & Service Provider Information Form
- (E) Subcontractor/Supplier/Installation & Service Provider Payment Notification Form
- (F) Example of a Release Letter

INTRODUCTION TO THE CITY OF CHARLESTON MUNICIPAL BUSINESS AND OCCUPATION TAX FOR CONSTRUCTION PROJECTS

Before starting any contracting work in the City of Charleston, all contractors must be registered with the Office of the City Collector ("City Collector"), and be current on all city taxes and fees. The Office of the City Collector is responsible for tracking and collecting all taxes and fees due on any and all construction projects in Charleston. If you are not currently registered with our office, but intend to perform construction work in the city, please complete a *Business Registration Application* and return it to our office.

The purpose of this Project Handbook is to educate individuals performing contracting activities in the City of Charleston of their Business and Occupation ("B&O") Tax responsibilities, as outlined in Chapter 110, Article II of the Code of the City of Charleston. Included in this handbook are pertinent sections of the state and city code regarding B&O taxes as they relate to contracting activities. In addition, we have also included examples of various forms and documents utilized by our office in our continuing effort to monitor and track your project throughout the construction process.

Any construction project with an estimated cost of \$50,000 or more will be monitored and tracked by our Tax Compliance staff. A Tax Compliance Officer will work closely with you throughout the duration of the project. In order to determine the proper amount of taxes and fees due, we will request complete lists of payments you received during the course of the project, as well as any and all payments made to subcontractors, service providers (architects, engineers, etc.), and suppliers, if applicable.

If you employ, utilize, or enter into a separate contract with any subcontractors, you should withhold at least two percent (2%) of the final contract amount from all subcontractors until a release is issued from the Collectors Office certifying that all taxes and fees due, including final payment/retainage, on this project have been reported/paid. Although the final payment/retainage may not have been issued to the subcontractor, the 2% B&O Tax on the final payment/retainage must be paid prior to the issue of an authorization to release funds. Please complete a *Subcontractor/Supplier/Installation & Service Provider Information Form* (see appendix D) for each contractor, supplier, installation & service provider you will be using.

We will make every effort to collect the taxes and fees due from your subcontractors. If they fail to report/pay their taxes and fees, you will be held responsible for their liability. Therefore, it is in your best interest as a general contractor, to make sure that all subcontractors that you hire are made aware of their B&O Tax liability to the City.

In addition to registering with the City Collector, all contractors must register with and obtain a contractor's license from the City Building Department. If you have any questions regarding your contractor license, please contact the Building Department at 348-6833.

The City Collector and Building Department are located in City Service Center at 915 Quarrier Street, Suite 4. Their offices are open daily Monday through Friday, 8 a.m. until 5 p.m., except holidays. Both departments are ready to assist you with any questions you may have regarding your city responsibilities and obligations.

BUSINESS & OCCUPATION TAX OVERIEW

The City of Charleston broadly imposes a Business & Occupation ("B&O") Privilege Tax upon all persons for the act or privilege of engaging in business activities within the City. The term "business" shall include all activities engaged in or caused to be engaged in with the object of gain or economic benefit, either direct or indirect. In determining whether a business is engaged in for "direct or indirect economic gain or benefit", the lack of profit suffered in said activity is not relevant; nor is it material that the business was engaged in without profit as the primary motivation.

B&O Tax is measured by the application of rates against values of products, gross proceeds of sale, or gross income of the business, as the case may be. All persons engaging in business activities in Charleston are subject to the B&O Tax unless specifically exempted by Chapter 110, Article II, Section 110-63 of the Code of the City of Charleston.

Certain occupations and business activities are classified, and the classifications are significant inasmuch as the tax liability varies because of the different rates established for the types of business activities engaged in by the taxpayer. The business activity usually determines the taxable classification, and where different business activities are conducted, the taxpayer is liable for tax under each taxable classification involved. If you are uncertain as to your business activity or how your business should properly calculate the tax, please contact our office.

B&O Tax returns are due within one month following the end of the taxable quarter. Quarterly payments are due in April, July, October and January. Penalty and interest will be applied against any return that is received after these months. If you did not conduct business activity during a particular reporting period, you still **must file a "zero" return.**

BUSINESS & OCCUPATION TAX CONSTRUCTION FREQUENTLY ASKED QUESTIONS (FAQ'S)

Q. WHO IS REQUIRED TO FILE?

A. All persons who are engaged in business within the City of Charleston are required to file B&O Tax returns. Persons domiciled outside the city limits who (a) lease tangible personal property to lessees in the municipality, or (b) **perform construction or installation contracts in the municipality**, or (c) render services to others therein, are doing business in the municipality, irrespective of the domicile of such persons, and irrespective of whether or not such persons maintain a permanent place of business in Charleston.

Construction, Supplier, Installation or Service Contracts in the City of Charleston:

When the business involves a construction, supplier, installation or service contract in the City of Charleston, no deduction from the measure of the tax is permitted, even though the contractor is domiciled outside Charleston, and maintains a place of business outside the municipality.

Construction, Supplier, Installation or Service Contracts Outside the City of Charleston:

When the business involves a construction, supplier, installation or service contract outside the City of Charleston, the tax does not apply to any part of the income derived therefrom, even though the contractor is domiciled in Charleston, and maintains a place of business therein, which may contribute to the contract performed outside the municipality.

Q. I WAS HIRED BY A GENERAL CONTRACTOR ON A PROJECT, AM I STILL REQUIRED TO PAY B&O TAXES ON THIS PROJECT?

A. Yes. You are responsible for B&O Tax on any and all gross receipts you receive for performing contracting activities Charleston. This includes any and all work performed for a general contractor. The revenue received must be reported and the taxes due must be paid to the City in the quarter that the funds are received.

Q. MY BUSINESS IS ALREADY REGISTERED WITH THE STATE OF WEST VIRGINIA. DO I STILL NEED TO REGISTER WITH THE CITY OF CHARLESTON?

A. Yes. The City is a separate and distinct entity from the State of West Virginia.

Q. WHAT IS GROSS INCOME?

A. Gross income means the gross receipts of the taxpayer, without any deduction on account of the cost of property sold, the cost of materials used, labor costs, taxes, royalties paid in cash or in kind or otherwise, interest or discount paid or any expense whatsoever.

Q. WHAT IS THE CONTRACTING TAX RATE?

A. Any and all gross receipts from contracting activities are taxed at two percent (2%).

Q. WHEN ARE B&O TAX RETURNS DUE?

A. The returns are due within one month following the end of the taxable quarter. Quarterly payments are due in April, July, October and January. Penalty and interest will be applied against any return that is received after these months.

Q. WHAT ARE THE PENALTY & INTEREST RATES?

A. The tax, if not paid when due, shall bear interest at the rate of 8% per annum from the date the return is due. The penalty shall be 5% for the first month, or fraction thereof, and 1% of the tax for each succeeding month or fraction thereof.

Q. AM I REQUIRED TO FILE EVEN IF I HAD NO INCOME DURING A PERIOD?

A. Yes. If you registered with the City, but have no business activity during a particular reporting period, you still must file a "zero" return.

Q. CAN I USE MY CREDIT OR DEBIT CARD TO PAY THE TAX?

A. Yes. Payments can be made on-line at <https://charlestonwvpayments.com>

Q. IS THERE A FEE FOR PAYING ON LINE?

A. Yes. The City of Charleston utilizes the services of Govolution, a third-party provider to process credit card, branded debit card and ACH payments via this website. Govolution will charge a non-refundable convenience fee per transaction. The convenience fee will vary, depending on the payment type and method of payment. The convenience fee is separate from the primary obligation you are paying and will appear on your statement as a charge to 'Govolution'. For a complete list of fees please visit our website: <https://charlestonwvpayments.com/payment-fees>

Q. WHAT IF I OVERPAID THE TAX, CAN I RECEIVE A REFUND?

A. Yes. Any taxpayer claiming to have overpaid any tax, interest, or penalty shall file a claim in writing to the City Collector within three years after the due date of the return or within two years from the date the tax was paid, whichever such period expires the later, or if no return was filed by the taxpayer, within two years from the time the tax was paid.

Q. WHAT IF I UNDERPAY OR FAIL TO PAY THE TAX?

A. If you underpay or fail to pay the tax, the City Collector may, at any time, issue an assessment. Upon receiving an assessment, you have thirty (30) days to: (1) remit the assessment balance due, or (2) contest the assessment and file a Petition for Reassessment, either in person or via certified mail. If you fail to comply with either number (1) or (2) above, the assessment will become final and conclusive, and a lien will be filed against you.

STATE OF WEST VIRGINIA CODE

FOR

CONSTRUCTION PROJECTS

WEST VIRGINIA CODE: TITLE 110, SERIES 26

Title 110-26-2	Imposition of privilege tax
Title 110-26-11	Doing business within and without the municipality
Title 110-26-1a.20	Definitions
Title 110-26-2e	Contracting

West Virginia Code Title 110-26-2. IMPOSITION OF PRIVILEGE TAX

2.1 The municipal business and occupation tax is a tax imposed upon persons for the act of privilege of engaging in business activities. The tax is measured by the application of rates against values of products, gross proceeds of sale or gross income of the business, as the case may be.

2.1.1 All persons engaging in business activities in a municipality which has ordinances providing for a municipal business and occupation tax pursuant to the authority granted by the Legislature in W.Va. Code §8-13-5 are subject to the municipal business and occupation tax unless specifically exempted by statute or by these rules and regulations.

2.1.2 Certain occupations and business activities are classified, and the classifications are significant inasmuch as the tax liability varies because of the different rates established for the types of business activities engaged in by the taxpayer. The business activity usually determines the taxable classification, and where different business activities are conducted, the taxpayer is liable for tax under each taxable classification involved.

West Virginia Code Title 110-26-11. DOING BUSINESS WITHIN AND WITHOUT THE MUNICIPALITY

11.1 Persons domiciled outside a municipality who (a) lease tangible personal property to lessees in the municipality, or (b) perform construction or installation contracts in the municipality, or (c) render services to others therein, are doing business in the municipality irrespective of the domicile of such persons and irrespective of whether or not such persons maintain a permanent place of business in the municipality.

11.2 Persons domiciled outside a municipality who sell tangible personal property to persons in the municipality, may be doing business in the municipality, irrespective of the domicile of such persons and irrespective of whether or not such persons maintain a permanent place of business in the municipality.

11.3 Persons domiciled in and having a place of business in a municipality, who (a) sell or lease personal property to buyers or lessees outside the municipality, or (b) perform construction or installation contracts outside the municipality, or (c) render services to others outside the municipality, are doing business both within and without the municipality. Whether or not such persons are subject to municipal business and occupation tax under the law depends upon the kind of business and the manner in which it is transacted. The following general principles govern in determining tax liability under the municipal business and occupation tax.

11.3.1 When the business involves a construction or installation contract in the municipality, no deduction from the measure of the tax is permitted, even though the contractor is domiciled outside the municipality and maintains a place of business outside the municipality which may contribute to the contract performed in the municipality.

11.3.2 When the business involves a construction or installation contract outside the municipality, the tax does not apply to any part of the income derived therefrom (except such part of the income as may be applicable to the manufacturer in the municipality by the contractor or articles used or incorporated in such construction or installation), even though the contractor is domiciled in the municipality and maintains a place of business therein which may contribute to the contract performed outside the municipality.

CODE OF THE CITY OF CHARLESTON

BUSINESS & OCCUPATION PRIVILEGE TAX

CODE OF THE CITY OF CHARLESTON: SECTION 110

Section 110-63	Computation of tax; quarterly payments; exemptions; return and remittance; extensions of time/payment plans: records, statements and investigations
Section 110-35	Revocation of Licenses and Permits
Section 110-145	Interests and penalties
Section 110-148	Final settlement with contractors; user personally liable.

Code of the City of Charleston Section 110-31. DEFINITIONS

Gross income means the gross receipts of the taxpayer, other than a banking or financial business, received as compensation for personal services and the gross receipts of the taxpayer derived from trade, business, commerce or sales and the value proceeding or accruing from the tangible property (real or personal) or service, or both, and all receipts by reason of the investment of the capital of the business engaged in, including rentals, royalties, fees, reimbursed costs or expenses or other emoluments, however designated, and including all interest, carrying charges, fees or other like income, however denominated, derived by the taxpayer from repetitive carrying of accounts, in the regular course and conduct of his business, and extension of credit in connection with the sale of any tangible personal property or service, and without any deduction on account of the cost of property sold, the cost of materials used, labor costs, taxes, royalties paid in cash or in kind or otherwise, interest or discount paid or any other expense whatsoever. "Gross income" of a banking or financial business is specified in section 110-60.

Contracting means to include the furnishing of work, or both materials and work, in the fulfillment of a contract for the construction, alteration, repair, decoration or improvement of a new or existing building or structure, or any part thereof, or for the alteration, improvement or development of real property.

Prime contractor means a person engaged in the business of performing for others, contracts for the construction, repairing, decorating or improving of new or existing buildings or other structures under, upon or above real property either for the work or for a specific portion thereof. The terms "prime contractor" and "subcontractor" include, but are not limited to, persons performing labor and services in respect to the moving of earth or clearing of land, razing or moving existing buildings or structures even though such services may not be done in connection with a contract involving the constructing, repairing, or altering of a new or existing building or structure.

Subcontractor means a person engaged in the business of performing a like or similar service for persons other than consumers, either for the entire work or for a specific portion thereof.

Buildings or structures means and includes, but is not limited to, everything artificially built up or composed of parts joined together in some definite manner and attached to real property. It includes not only buildings in the general and ordinary sense, but also tanks, fences, conduits, culverts, railroad tracks, overhead and underground transmission systems, tunnels, monuments,

retaining walls, bridges, trestles, parking lots and pavement for foot or vehicular traffic. *Contracting, repairing, decorating or improving* means of a new part of an existing building or structure or any part thereof, in addition to its ordinary meaning includes, but is not limited to, the installing or attaching of any article of tangible personal property in or to real property, whether or not such personal property becomes a part of the realty by virtue of such installation.

Code of the City of Charleston Section 110-56. BUSINESS OF CONTRACTING

(a) Upon every person engaging or continuing within the city in the business of contracting, the tax shall be equal to two percent of the gross income of the business. A person performing any contracting activity shall report his/her gross income therefrom under the contracting classification of the municipal business and occupation tax return and shall receive no deduction from gross income on the account of any expenses incurred. All income derived from said activity shall be reported under the contracting classification, and the form of contract entered into by the parties shall not be determinative of taxable classification.

(b) Form of contract. Persons engaged in the contracting business shall report the entire gross income under the contracting classification, regardless of whether the contract is a turnkey contract, lump sum contract, per unit contract, cost plus fixed fee contract, or other contract having a similar basis. Gross income received from a contracting activity must be reported under the contracting classification and the manner of performance, basis of determining cost, fee or income or form of contract shall not alter the definition of contractor or of contracting and shall not change the taxability of such income from the contracting classification to another classification. A contracting activity remains a contracting activity regardless of what the parties may name it and regardless of the manner in which the parties may make payment and perform work.

(c) Costs. The measure of the tax under the contracting classification is gross income and includes all items of cost where the contractor has incurred liability. The cost of materials and labor can only be exempted from the measure of the tax in those cases where the contractor is not liable to vendors or workmen for payment. In those cases where the contractor contends that he/she has not incurred a municipal business and occupation tax liability because he/she acted solely as an agent for the owner, the burden of proving alleged principal-agency relationship shall be upon the contractor.

(d) Separate contracts for labor and materials. In cases where the contractor enters into a separate contract for the furnishing of materials by the contractor and a separate contract for erection of such materials by the contractor, the gross income from both contracts is taxable under the contracting classification, unless it can be provided by the contractor that passage of title of the materials was not dependent upon the erection of the materials by the contractor and that the sale of such materials is, in fact, a separate and distinct transaction, taxable under the municipal business and occupation tax law, as a retail or wholesale sale, as the case may be. The contract to furnish materials shall not be considered a separate and distinct transaction from the contract to erect the same, unless it is established by the contractor to be a complete arm's length transaction with no dependency existing between the contract for materials and the contract for erection. The burden of proving any alleged arm's length transaction shall be upon the contractor.

(e) Separate purchase orders. A separate purchase order for the furnishing of work or labor and a separate purchase order for the furnishing of materials which constitutes the contract(s) between the parties shall be treated in the same manner as set forth in the paragraph above.

(f) Prime and subcontractors. A prime contractor, one who furnishes work or both materials and work under a written or oral contract, for the construction, alteration, repair, decoration or improvement of a new or existing building or structure or any part thereof, or for the alteration,

improvement or development of realty, must report his/her gross income under the contracting classification without any deduction on account of any expenses incurred. If the prime contractor executes a contract with another for a portion of the job or project, the prime contractor receives no deduction from gross income on account of any payment made to the subcontractor. The subcontractor will also be taxed on his/her gross income under the contracting classification.

(g) Contract entered into with government. Gross income received by a person for contracting activities performed for the State of West Virginia, the federal government or any of their instrumentalities, agencies, boards, commissions or political subdivisions, etc., or performed for nonprofit organizations is taxable and shall be reported under the contracting classification. The fact that the owner is a governmental unit or a non-profit organization does not relieve the contractor, subcontractor, supplier or any other person from liability for municipal business and occupation tax on the full amount of gross income.

Code of the City of Charleston Section 110-63. EXEMPTIONS

(a) The provisions of this article shall not apply to:

(1) Insurance companies which pay the state a tax upon premiums; provided, that such exemption shall not extend to that part of gross income of insurance companies which is received for the use of real property, other than property in which any such company maintains its office or offices, in the city, whether such income is in the form of rentals or royalties;

(2) Nonprofit cemetery companies organized and operated for the exclusive benefit of their members;

(3) Fraternal societies, organizations and associations organized and operated for the exclusive benefit of their members and not for profit; provided, that this exemption shall not extend to that part of gross income arising from the sale of alcoholic liquor, food and related services of such fraternal societies, organizations and associations which are licensed as private clubs under the provisions of W. Va. Code Ch. 60, Art. 7;

(4) Corporations, associations and societies organized and operated exclusively for religious or charitable purposes;

(5) Production credit associations, organized under the provisions of the federal Farm Credit Act of 1933; provided, that the exemptions of this section shall not apply to corporations or cooperative associations organized under the provisions of W. Va. Ch. 19, Art. 4;

(6) Any credit union organized under the provisions of Chapter 31 or any other chapter of the Code of West Virginia; provided, that the exemptions of this section shall not apply to corporations or cooperative associations organized under the provisions of W. Va. Ch. 19, Art. 4;

(7) Gross income derived from advertising service rendered in the business of radio and television broadcasting;

(8) The gross income or gross proceeds of sale of a gasification or liquefaction of coal project in the demonstration, pilot or research states; provided, that prior to the commencement of operation of any such project, the tax commissioner of the state shall have first certified the project as eligible for such exemption; provided, further, that such exemption shall expire seven years from the date the project first receives gross income or gross proceeds from sales; and

(9) The gross income or gross proceeds of sale derived from sales or services by an itinerant vendor or a street vendor in cases where no itinerant vendor license or street vendor license is required by City Code Sections 18-613 or 18-1033.

(b) An organization is "charitable" for purposes of (4) above it satisfies both of the following criteria: (1) it is exempt from Federal Tax, under 26 U.S.C. § 501(c)(3), and (2) its purposes include relief of poverty, advancement of education, advancement of religion, promotion of health, governmental or municipal purposes, or other purposes that are beneficial to the community.

Code of the City of Charleston Section 110-81. TAX CUMULATIVE

(a) The tax imposed by this article shall be in addition to all other licenses and taxes levied by law as a condition precedent to engaging in any business, trade, calling or activity. A person exercising a privilege taxable under this article, subject to the payment of all licenses and charges which are a condition precedent to exercising the privilege tax, may exercise the privilege for the current tax year upon the condition that he shall pay the tax accruing under this article.

(b) Computation of tax.

(1) The taxes levied hereunder shall be due and payable in quarterly installments on or before the expiration of one month from the end of the quarter in which they accrue. The taxpayer shall, within one month from the expiration of each quarter, make a return reporting the tax for which he/she is liable for such quarter; sign it and mail it, together with any remittance due, in the form required by Section 110-82 of the amount of the tax to the office of the city collector. When the total tax for which any person is liable under this article does not exceed the sum of \$200.00 in any year, the taxpayer may pay the tax quarterly as aforesaid or, with the consent in writing of the city collector, at the end of the month next following the close of the tax year.

(2) The city collector, if he deems it necessary, based upon past experience with a taxpayer, based on the past practices of a taxpayer, based on the financial condition of the taxpayer, or based on the size of the contract, in order to insure payment of the taxes levied hereunder, may require return and payment under this section for other than quarterly periods. Furthermore, if the city collector deems it necessary to insure payment of the business and occupation tax, he may require a deposit to be paid by the taxpayer prior to when the taxes accrue and are otherwise payable. The amount of the deposit shall be determined and/or based upon the taxpayer's projected gross income or gross proceeds of sale for the applicable tax period. This deposit shall be paid to the office of the city collector, at a date and time, and in a manner determined by the city collector.

(3) Every contractor whose principal business location is outside of the city, shall register with the city collector prior to engaging in the performance of a contract in this city, and the city collector, if he deems it necessary, based on the past experience with a taxpayer, based on the past practices of a taxpayer, based on the financial condition of the taxpayer, or based on the size of the contract, in order to insure payment of the taxes levied hereunder, may also require the following:

(a) At the time of registration, each contractor shall deposit with the city collector six percent of the amount the contractor is to receive for the performance of the contract, which sum shall be held within a contractor's use tax fund pending the completion of the contract.

(b) In lieu of the six percent deposit, each contractor may request the approval of the city collector to provide, in the alternative, a corporate surety bond to be approved by the city collector as to form, sufficiency, value, amount, stability, and other features necessary to provide a guarantee of payment of the tax due the city.

Code of the City of Charleston Section 110-82. RETURN AND REMITTANCE; TAX YEAR

(a) On or before 31 days after the end of the tax year, each person liable for the payment of a tax under Section 110-51 shall make a fourth quarter return, showing the gross proceeds of sale or gross income of business, trade, calling or activity, computing the amount of tax chargeable against him in accordance with the provisions of this article and transmit with his report a remittance in the sum required by this section, covering the remainder of the tax chargeable against him, in the office of the city collector. Such returns shall be verified by the oath of the taxpayer, if made by an individual, or by the oath of the president, vice president, secretary or

treasurer of a corporation, if made on behalf of the corporation. If made on behalf of a partnership, joint venture, association, trust or any other group or combination acting as a unit, any individual delegated by such firm, group or unit shall take the oath on behalf of the taxpayer.

(b) The assessment of taxes herein made and the returns required therefore shall be for the year ending December 31. If the taxpayer, in exercising a privilege taxable under this article, keeps the books reflecting the same on the basis other than the calendar year, he may with the written consent of the city collector, make his annual returns and pay taxes for the year covering his accounting period, as shown by the method of keeping his books.

(c) All remittances of taxes imposed by this article shall be made to the city collector, in lawful money of the United States or by bank draft, certified check, cashier's check, money order or certificate of deposit, who shall pay the money into the city treasury, to be kept and accounted for as provided by law.

Code of the City of Charleston Section 110-83. EXTENSIONS OF TIME; PAYMENT PLANS

(a) The city collector, upon approval from city manager, may grant a reasonable extension of time for payment of tax or any installment, or for filing the fourth quarter return or quarterly return required pursuant to this article, on such terms and conditions that he may require. No such extensions shall exceed six months.

(b) The city collector, upon approval from city manager, may extend the time for payment of an amount determined as a deficiency for a period not to exceed 12 months from the date designated for payment of the deficiency. An extension of this time may be granted only where it is clearly established to the satisfaction of the city collector that the payment of a deficiency upon the date designated for payment would result in undue hardship.

(c) If any extension of time is granted for payment of any tax or deficiency, the city collector may require the taxpayer to furnish a bond or other security, in an amount not exceeding twice the amount for which the extension of time for payment is.

Code of the City of Charleston Section 110-84. RECORDS, STATEMENTS AND INVESTIGATIONS

(a) For the purpose of ascertaining the correctness of a tax return or an assessment for the purpose of making an estimate of any taxpayer's liability for the tax administered under this article, the city collector shall have the power to examine or cause to be examined, by any agent or representative designated by the city collector, any books, papers, records, memoranda or other documents bearing upon the matters required to be included in the return and may require the attendance of the person rendering the return or the attendance of any other person having knowledge of the matters contained therein. In connection therewith, the city collector may take testimony and shall have the power to administer an oath to such person.

(b) The city collector may prescribe rules and regulations as to the keeping of records, the content and form of returns and the filing of copies of city business and occupation tax returns and determinations. The city collector may require any person, by notice served upon such person, to make such returns and keep such records as the city collector may deem sufficient to show whether or not such person is liable under this article for such tax.

Code of the City of Charleston Section 110-35. REVOCATION OF LICENSES AND PERMITS

(a) The city collector has the authority to revoke any and all licenses and permits issued by the

city in the event a licensee/permittee fails to file any city tax return or fails to pay any delinquent taxes, fees or any interest or penalty thereon due and owing to the city. The city collector has the authority to deny and prevent any and all licenses and permit privileges to those persons who are delinquent in paying taxes, fees or any interest or penalty thereon due and owing the city.

(b) In the event of revocation, the city collector will provide written notice to the licensee/permittee at least five days prior to the contemplated revocation and such notice shall be served by certified mail. The notice shall indicate the time and the place of the revocation review meeting, the general grounds of said contemplated revocation, and shall advise the licensee/permittee of his/her rights to appear at said hearing in person and represented by legal counsel, and to be heard orally upon the merits of his/her defense. The city collector may request legal advice from the city attorney's office, and adopt such procedures for its decorum and the dispatch of business at such hearings as he/she may regard advisable. The revocation decision of the city collector will be final; provided, that those licensees/permittees who are subject to administrative or judicial appeals, pursuant to Sections 110-113 through 110-115, may utilize these procedures in accordance with the Code, but will not be grounds to delay the revocation process.

(c) Each license or permit that has been revoked pursuant to this section may be re-issued upon payment of all delinquent B&O taxes, fees or any interest or penalty thereon due and owing to the city.

Code of the City of Charleston Section 110-145. INTEREST AND PENALTIES

(a) The tax imposed by this article, if not paid when due, shall bear interest at the rate of at least eight percent per annum from the due date of the return until paid. The city collector may charge an interest rate equal to the adjusted rate charged by commercial banks to large business, in the manner described in W. Va. Code § 11-10-17a.

(b) If any taxpayer fails to make the return or any quarterly installment required by this article, or make his return but fails to remit, in whole or in part, the proper amount of tax, there shall be added to the amount of tax unpaid, from the date such tax should have been paid, a penalty in the amount of five percent of the tax for the first month, or fraction thereof, of delinquency, and one percent of the tax for each succeeding month, or fraction thereof of delinquency provided, that if such failure is due to reasonable cause, the city collector may waive, with final approval from the city manager, in whole or in part, these penalties. Additionally, if the failure to pay is due to fraud or intent to evade any such tax there shall be added an additional penalty of 25 percent of the tax owed, exclusive of penalties.

(c) Interest and penalties may be collected in the same manner as the tax imposed by this article.

Code of the City of Charleston Section 110-148. FINAL SETTLEMENT WITH CONTRACTORS; USER PERSONALLY LIABLE

(a) Any person contracting with a person engaged in a business or service taxed under this article shall withhold payment, in sufficient amount to cover taxes assessed by this article, in the final settlement of such contracts until the receipt of a certificate from the city collector to the effect that all taxes levied and accrued under this article against the contractor have been paid.

(b) If any person shall fail to withhold as provided herein, he shall be personally liable for the payment of all such taxes, and the same shall be recoverable by the city collector by appropriate legal proceedings.

**PROCEDURES FOR
AUTHORIZATION TO RELEASE
FINAL PAYMENT/RETAINAGE**

1. The general/prime contractor is the only one that may request an authorization to release final payment/retainage for their subcontractors.
2. A written request must be submitted to the Office of City Collector containing the following information:
 - a) The final contract amount(s) plus any amount(s) not under contract.
 - b) The date(s) and amount(s) of each payment made to all subcontractors.
 - c) The amount(s) held as final payment/retainage.
3. Upon receiving the aforementioned information from the general contractor, the Office of City Collector will request the following information from each subcontractor:
 - a) The final amount paid to you by the general/prime contractor (final contract amount, final paid to date and final payment/retainage).
 - b) The date(s) and amount(s) of each payment you received from the general/prime contractor, and the quarter the Business and Occupation Tax was reported/paid.
 - c) The names and addresses of any subcontractor(s) utilized, if applicable.

EXAMPLE:

<u>Date Received</u>	<u>Amount Received</u>	<u>Qtr. Reported</u>
1/06/04	\$2,000.00	1/04
6/10/04	\$3,000.00	2/04
Retainage	\$ 500.00	Not Reported

4. After receiving the requested information from the subcontractor(s), the Office of City Collector will send the general/prime contractor a *RELEASE APPROVAL* letter stating **all** B & O taxes have been reported/paid on the project, or a *RELEASE DENIAL* letter stating the tax, penalty and interest due on the project. A copy of this letter will also be sent to the subcontractor.

RTS ACCOUNT #: _____

B&O: Yes / No

CSF: Yes / No

BL: Yes / No

License Fees: _____

Penalty: _____

TOTAL PAID: _____

City Official Use Only

BUSINESS REGISTRATION

City of Charleston
915 Quarrier St., Suite 4
Charleston, WV 25301
Phone: (304)348-8024
Fax: (304)347-1810
www.charlestonwv.gov



IMPORTANT: This is a four-page application. All applicable questions must be answered in order to properly classify business activities. Incomplete forms will delay the processing of your application.

Section I. General Information:

1. Company Name: _____

2. DBA: _____

3. Federal Employer ID/Social Security Number*: _____

4. Physical Address of Business: _____

5. City: _____ 6. State: _____ 7. Zip Code: _____

8. Physical Location Phone Number: _____

9. Contact Name: _____ Contact Email: _____

10. Contact Phone Number: _____ Fax: _____ Mobile: _____

11. Mailing Address: _____

12. City: _____ 13. State: _____ 14. Zip Code: _____

15. Ownership Type:

_____ Proprietorship _____ Partnership _____ Corporation _____ Non-Profit _____ Other
(Include copy of 501(c)(3))

16. Description of Business: _____

17. Date Business Began Operation in Charleston: _____

18. Do you have an employee(s) working out of their home that is located within the city limits of Charleston? Yes / No

If you answered yes to question # 18, please provide a description of the employee(s) job duties including whether or not the job functions generate revenue for the business: _____

RTS ACCOUNT # : _____

City Official Use Only

19. Does this business own the property on which it is located? Yes / No

If not, who is the owner? _____

Owner's address _____

Owner's phone ## _____

20. Does your business contain vending machines? _____ If so, who is the owner and their address?

*****If you answer **YES to Any** of the questions below **complete Pages 1 - 4** of this application*****
If you answer **NO to All** of the questions below only **complete Pages 1 & 2**

21. Do you have a physical location in Charleston? Yes / No

22. Is this a Home Based Business: Yes / No **Home Based Business-** A business that is operated out of a personal residence.

23. Do you own more than 1 rental unit in the City of Charleston? Yes / No If Yes, how many units: _____

Please attach a sheet listing all rental property that you own in the City of Charleston and indicate for each if the rental is for short term (less than 30 days) or long term.

List all principle officers, proprietors, partners or any individual owning more than 25% of the business:

Name _____ Social Security # _____

Address _____ Telephone # _____

Name _____ Social Security # _____

Address _____ Telephone # _____

Name _____ Social Security # _____

Address _____ Telephone # _____

***Privacy Act Statement**

Disclosure of a Social Security Number (SSN) to the City of Charleston is voluntary. If you do not wish to disclose your SSN, you may provide an alternative identification number. The City of Charleston solicits this information pursuant to West Virginia Code § 8-13-13 and the Charleston City Code. The City of Charleston will not disclose your SSN or any other information you provide to any other entity or party.

Authorized Signature of Business: By signing below, I do hereby certify and declare, under penalty of perjury, that the information furnished in this application is true, complete and accurate to the best of my knowledge.

Signature of Business Owner or Authorized Agent

Date

Title

RTS ACCOUNT # : _____

City Official Use Only

Section II. Business License Category: (Only complete this section if you answered yes to Question #21, #22, or #23)

1. Select the appropriate license(s) for your business in **Part A**. All businesses with a storefront or a physical location within the City of Charleston are required to purchase a General Business License. Sales of beer or liquor require an additional license. If your business intends to sell beer or liquor, you **must** attach a copy of your WV ABCC License.
2. Complete **Part B** in its entirety. If your business intends to sell or serve prepared food, you **must** attach a copy of your Kanawha County Health Permit. If your business desires to purchase gold, silver or other precious metals, jewels or other products, you **must** comply with the requirements of §18-863 of the Charleston Municipal Code to report your purchases to the Charleston Police Department. If your business intends to conduct door-to-door sales or engage in home solicitation, a \$3,000 surety bond **must** be posted for **each** sales representative.
3. Sign and date the application in Part C.

Part A:

General Business:

☐ **0. GENERAL BUSINESS (\$20.00)**

Beer - Must attach valid WV ABCC License

- ☐ 1. Distributor (\$250.00)
☐ 2. Dispenser (\$100.00)
☐ 4. Class A Retail (\$100.00)
☐ 5. Class B Retail (\$15.00)

Liquor - Must attach valid WV ABCC License

- ☐ 6. Private Club Less than 1000 members (\$500.00)
☐ 7. Private Club More than 1000 members (\$1,250.00)
☐ 8. Fraternal, Veterans or Non -Profit Social Clubs (375.00)

Part B:

- A. Does your business **purchase** gold, silver or other precious metals, jewels or products? Yes / No
If yes, see City Code §18-863
- B. Does your business **sell**? **Beer:** Yes / No **Liquor:** Yes / No **If Yes, you Must attach your ABCC license.**
- C. Does your business **sell** or serve prepared food? Yes / No **If Yes, you Must attach a copy of your Kanawha County Health Permit.**
- D. Does your business conduct home solicitations or door-to-door sales? Yes / No
If Yes, you Must post a \$3,000 surety bond for each sales representative.

Part C: Authorized Signature of Business: By signing below, I do hereby certify and declare, under penalty of perjury, that the information furnished in this application is true, complete and accurate to the best of my knowledge.

Signature of Business Owner or Authorized Agent

Date

Title

RTS ACCOUNT # : _____

City Official Use Only

Section III. Planning/Zoning & Property Certification:

It is the responsibility of each applicant upon an **initial** application for a city business license/registration to first ascertain inspection and approval for occupancy of the premises from the Planning/Zoning, Building and Fire Departments. **The information in the box below is for a new business, an existing business with a new owner, or an existing business in a new location within the City of Charleston.**

Do Not Write Inside This Box—For City Official Use Only

TO BE COMPLETED BY: ZONING/PLANNING DEPARTMENT

Phone Number: (304)348-8105

1. Was the business location previously occupied? ☐ Yes ☐ No
2. Is the proposed business a continuation of that previous type of business? ☐ Yes ☐ No
3. Has the applicant confirmed the zoning of this location? ☐ Yes ☐ No
4. Does this business conform to the current zoning code? ☐ Yes ☐ No
5. What is the Zoning District of this proposed business: _____
6. Applicable Section of the Zoning Ordinance: _____
7. Has the Planning Office approved the proposed business? ☐ Yes ☐ No

If no, the reasons are as follows: _____

Approved By: _____
Planning Official

Date: _____

TO BE COMPLETED BY: BUILDING DEPARTMENT

PHONE NUMBER: (304)348-6833

Approved By: _____
Building Official

Date: _____

TO BE COMPLETED BY: FIRE DEPARTMENT

PHONE NUMBER: (304)348-8058

Approved By: _____
Fire Department Official

Date: _____



BUSINESS AND OCCUPATION TAX RETURN CITY OF CHARLESTON

P.O. Box 7786

CHARLESTON, WV 25356

Phone: (304)348-8024 Fax: (304)347-1810

Pay online at: www.charlestonwvpayments.com



THIS SECTION MUST BE COMPLETED

ACCOUNT #: _____ TAX QUARTER: _____

BUSINESS NAME: _____

ADDRESS: _____

PHONE#: _____

SEE REVERSE
FOR INSTRUCTIONS



Revised 10/2022

COMPUTATION OF QUARTERLY TAX

CLASS CODE	BUSINESS CLASSIFICATION	GROSS AMOUNT	RATE MULTIPLIER	TAX DUE
1	Value of Production of Natural Resources (1%)		0.01	
3	Retailers (1/2 of one percent)		0.005	
4	Wholesalers (15/100 of one percent)		0.0015	
5	Electric Power Companies (4%) <small>(sales & demand charges domestic purposes & commercial lighting)</small>		0.04	
6	Electric Power Companies (3%) <small>(all other sales & demand charges)</small>		0.03	
7	Natural Gas Companies (3%)		0.03	
8	Water Companies (4%)		0.04	
9	All Other Public Utilities (2%)		0.02	
10	Contracting* (2%) <small>(totals from worksheet on back)</small>		0.02	
11	Amusement (1/2 of one percent)		0.005	
12	Service & All Other Business (1%)		0.01	
13	Rents & Royalties (1%)		0.01	
14	Banking & Other Financial Institutions (1%)		0.01	
TOTAL TAX DUE				

*If you are reporting contracting income, you must complete worksheet A on back of form.



PLEASE CHECK BOX IF ADDRESS
HAS CHANGED.

UNDER PENALTIES OF PERJURY, I DECLARE
THAT I HAVE EXAMINED THIS RETURN AND TO
THE BEST OF MY KNOWLEDGE AND BELIEF IT
IS TRUE, CORRECT AND COMPLETE

A SERVICE FEE WILL BE CHARGED
FOR ALL RETURNED CHECKS.

THIS RETURN WITH PAYMENT TO COVER TAX DUE MUST BE
RECEIVED WITHIN ONE MONTH FROM END OF PERIOD COVERED.

TYPE OR PRINT NAME AND TITLE OF PREPARER

X

PREPARER'S SIGNATURE AND DATE

SIGNATURE REQUIRED

OFFICE USE ONLY

INSTRUCTIONS

1. Determine your Business Classification(s) and corresponding rate(s) from the tax table.
2. Determine your Charleston B&O taxable gross income for each of the classifications and enter it in the appropriate box. (Contracting class instructions are listed below.)
3. Determine your taxes due by multiplying the rate by the taxable income.
(example: \$10,000 in gross taxable income times a service rate of 1.00% or .01 equals a B&O tax due of \$100). **Failure to complete this form in its entirety and/or enclose your remittance may result in your return being sent back to you.**
4. **Sign the return. THIS RETURN IS INVALID UNLESS IT IS SIGNED.**
5. If your name and/or address printed on the form is incorrect, please mark through the incorrect information and write the correct information in the open space.
6. **If your business or rental property has been closed or sold, please send a written statement detailing the status of the business, the date of the change, and requesting the account be closed or put on our inactive list.**
7. If your return is postmarked after the due date, you will be sent a letter for penalties and interest due.
8. Please make checks payable to: City of Charleston
9. Mail payments and/or correspondence to: City Collectors Office, P.O. Box 7786, Charleston, WV 25356
10. If you have any questions, please call us at (304) 348-8024 or via email at www.charlestonwv.gov

TO BE COMPLETED BY CONTRACTORS ONLY

PROJECT NAME	GROSS TAX AMOUNT	TAX RATE	TAX DUE
		2%	
		2%	
		2%	
		2%	
		2%	
		2%	
		2%	
		2%	
		2%	
TOTALS			

CONTRACTING INSTRUCTIONS

1. Please complete one line for each project that you received payment (if additional lines are needed please attach an additional letter).
2. List the name of the project, the gross amount received and calculate the tax amount due.
3. Transfer the total tax amount due to the front of the return in the contracting (class code 10) tax due field.

Privacy Statement Act

Disclosure of a Social Security Number (SSN) to the City of Charleston is voluntary. If you do not wish to disclose your SSN, you may provide an alternative identification number. The City of Charleston solicits this information pursuant to West Virginia Code § 8-13-13 and the Charleston City Code. The City of Charleston will not disclose your SSN or any other information you provide to any other entity or party. The City of Charleston requests this information to facilitate the verification of withholding and payment of service fees.



CITY SERVICE FEE RETURN

CITY OF CHARLESTON, WV

P.O. Box 7786

CHARLESTON, WV 25356

Phone: (304)348-8024 Fax: (304)347-1810

www.charlestonwv.gov

Email: citycollector@cityofcharleston.org

THIS SECTION MUST BE COMPLETED

ACCOUNT #: _____

FEE QUARTER: _____

Business Name: _____

Mailing Address: _____

CSF REMITTANCE FORM

Form **CSF-2**

See instructions on the
reverse side of this form ►

(Rev 10/2022)

Basis of Computation (choose one)	Weekly <input type="checkbox"/> \$3.00	Bi-Weekly <input type="checkbox"/> \$6.00	Semi-Monthly <input type="checkbox"/> \$6.50	Monthly <input type="checkbox"/> \$13.00
--------------------------------------	----------------------------------------------	-------------------------------------------------	----------------------------------------------------	------------------------------------------------

	A	B	C
	Pay Period or Week Ending Date	Number of Employees/Self- Employed in Charleston	Fee Due
a			
b			
c			
d			
e			
f			
g			
h			
i			
j			
k			
l			
m			
Total Fee Due:			

☐ PLEASE CHECK BOX IF ADDRESS HAS CHANGED.

FOR OFFICE USE ONLY

UNDER PENALTIES OF PERJURY, I
DECLARE THAT I HAVE EXAMINED
THIS RETURN AND TO THE BEST OF
MY KNOWLEDGE AND BELIEF, IT IS
TRUE CORRECT AND COMPLETE

TYPE OR PRINT NAME AND TITLE OF PREPARER

X

PREPARER'S SIGNATURE AND DATE

SIGNATURE REQUIRED

A SERVICE FEE WILL BE CHARGED FOR ALL
RETURNED CHECKS

CSF Instructions for Employer and Self-Employed Remittance Form

1. Complete, sign and date this return. **Failure to complete this form in its entirety and/or enclose your remittance may result in your return being returned to you.**
2. This return must be accompanied by the required remittance no later than the last day of the month succeeding the close of each calendar quarter. Self-employed individuals may request authorization from the City Collector to remit the fees annually.
3. Employers must use this form to remit amounts withheld from employees and amounts received from certain self-employed persons who are members or partners of the Employer. Self-employed persons who are not members or partners of an Employer must use this form to remit the amount of City Service Fee due.
4. This form must be completed based on the **Basis of Computation Method** chosen by the Employer and disclosed on the front of this return, as explained in the administrative regulations.
5. The dates entered in lines "a" through "m", Column A shall be the ending dates for each weekly, bi-weekly, semi-monthly, or monthly pay period, depending on the period used and elected by the Employer, throughout the entire reporting period.
6. Enter the total number of employees/self-employed in Charleston during the pay period or week in Column B lines "a" through "m".
7. Multiply the number of employees/self-employed listed in Column B lines "a" through "m" by the appropriate rate (depending upon the Basis of Computation withholding method chosen) and list the total \$ amount in Column C lines "a" through "m".
8. Add the fee due amount in lines "a" through "m" Column C and enter the amount in the Total Fee Due line. This is the amount owed for the quarter.
9. **Sign the return. THIS RETURN IS INVALID UNLESS IT IS SIGNED.**
10. If your name and/or address printed on the form is incorrect, please mark through the incorrect information and write the correct information in the open space.
11. **Returns postmarked after the due date will be assessed penalty and interest due. An invoice for penalty & interest will be mailed to you.**
12. Please make checks payable to: City of Charleston
13. Mail payments and/or correspondence to: City Collector's Office, P.O. Box 7786, Charleston, WV 25356
14. For additional information, please refer to the City Service Fee Administrative Regulations available at www.charlestonwv.gov or call the Charleston City Collector's Office at (304)348-8024.

Please note that only this remittance form will be accepted. Any change or modification to this form will also result in your return being returned to you.

Privacy Statement Act

Disclosure of a Social Security Number (SSN) to the City of Charleston is voluntary. If you do not wish to disclose your SSN, you may provide an alternative identification number. The City of Charleston solicits this information pursuant to West Virginia Code § 8-13-13 and the Charleston City Code. The City of Charleston will not disclose your SSN or any other information you provide to any other entity or party. The City of Charleston requests this information to facilitate the verification of withholding and payment of service fees.

QUARTER	PERIOD	DUE DATE
1st qtr.	January 1st - March 31st	April 30th
2nd qtr.	April 1st - June 30th	July 31st
3rd qtr.	July 1st - September 30th	October 31st
4th qtr.	October 1st - December 31st	January 31st



OFFICE OF CITY COLLECTOR

915 Quarrier St., Suite 4 | Charleston, WV 25301 | (304) 348-8024 | (304) 348-0734 (fax)|
constructionprojects@cityofcharleston.org

SUBCONTRACTOR/SUPPLIER/INSTALLATION & SERVICE PROVIDER INFORMATION FORM

Please Print or Type

Company Name: _____
(Name of Subcontractor/Supplier/Installation or Service Provider)

Federal Employer Identification Number (FEIN): _____

Address: _____

Telephone: _____ Fax: _____ Cell: _____

Email: _____ Contract Amount \$ _____

General Contractor: _____

Project: _____

Brief Description of Work to be Performed: _____

Contract Date: _____ Start Date: _____

Do You Anticipate Change Orders? Yes___ No___ Don't Know___

Name and Phone Number of Contact Person Regarding This Contract:

Name _____ Phone _____

 Signature of Person Completing This Form

****Please Return to the Above Physical Address, Fax Number or Email Address****

SUBCONTRACTOR/SUPPLIER/INSTALLATION & SERVICE PROVIDER PAYMENT NOTIFICATION FORM

General

(COMPLETE QUARTERLY)

Contractor:

Quarter:

Name/Address of

Project:

(Appendix E)

Name, Address & Contact Information of the

Subcontractor/Supplier/Installation or Service Provider:

Total Contract Amount (\$):

Total Payment(s) Paid this Quarter (\$):

Total Payments Paid to Date (\$):

Name:			
Address:			
City, State, Zip:			
Contact Name & #:			
Name:			
Address:			
City, State, Zip:			
Contact Name & #:			
Name:			
Address:			
City, State, Zip:			
Contact Name & #:			
Name:			
Address:			
City, State, Zip:			
Contact Name & #:			
Name:			
Address:			
City, State, Zip:			
Contact Name & #:			
Name:			
Address:			
City, State, Zip:			
Contact Name & #:			

City of Charleston | City Collector's Office | Phone: (304)348-8026 x377 | Fax: (304)348-0734 | email: constructionprojects@cityofcharleston.org

(This form can be emailed to you upon request for online completion)

Revised 5/31/2017



(Appendix F)

OFFICE OF THE CITY COLLECTOR

915 Quarrier St., Suite 4 | Charleston, WV 25301 | (304) 348-8024 | (304) 348-0734 (fax)

September 18, 2015

John Doe Construction
Attn: Tax Department
1234 High Street
Charleston, WV 25302

RE: State Bank Building Project

Dear Mr. Doe:

This is to certify that as of September 18, 2015, the City of Charleston Business and Occupation Privilege Tax accrued on the gross income of \$80,000.00 for the aforementioned project against the hereinafter named taxpayer has been paid in full, based on returns filed by the taxpayer.

Jane Doe Construction
5678 River Road
Charleston, WV 25302

The execution of this letter is not based on an audit of the taxpayer's records, but only upon information available from a review of the taxpayer's file. If you have any questions, please feel free to contact City Employee, Tax Compliance Officer at (304) 348-8000, ext. 377 or via email at constructionprojects@cityofcharleston.org.

Sincerely,

City Employee
Tax Compliance Office
Office of the City Collector
City Of Charleston

CC: Jane Doe Construction Company